PRIME CONSULTANT:


# architecture inc. Χ


# CONSULTANT TEAM

ARCHITECT:	1x1 ARCHITECTURE INC 230 MAIN STREET, SUITE 310 WINNIPEG, MANITOBA, R3C 1A8 TEL: (204) 318-2010
STRUCTURAL ENGINEER	LAVERGNE DRAWARD & ASSOCIATES INC 193 DUMOULIN STREET WINNIPEG, MANITOBA, R2H 0E4 TEL: (204) 947-2222 FAX: (204) 947-2522
MECHANICAL + ELECTRICAL ENGINEER:	EPP SIEPMAN ENGINEERING INC. 400-136 MARKET AVENUE WINNIPEG, MANITOBA, R3B 0P4 TEL: (204) 453-1080 FAX: (204) 453-1335

## **ABBREVATIONS**

A/FL	ABOVE FLOOR
ALUM	ALUMINUM
ANOD	ANODIZED
BLDG	BUILDING
ВМ	BEAM
ВОТ, ВТМ	BOTTOM
B.S	BOTH SIDES
BTWN	BETWEEN
C.I.P	CAST IN PLACE
CL	CENTER LINE
C.P	CENTER POINT
C.L.F	CHAIN LINK FENCE
COL	COLUMN
C/W	COMPLETE WITH
CONC	CONCRETE
C.B	CONCRETE BLOCK
CJ	CONTROL JOINT
D DTL	DEEP
DTL	DETAIL DOWN
DWG, DRWG	DRAWING
EA	EACH
ELEV	ELEVATION
ELEC	ELECTRICAL
EPOX	EPOXY
EQ EQUIP	EQUAL
EQUIP	EQUIPMENT EXPOSED
EXT	EXTERIOR
FD	FLOOR DRAIN
F.H.C	FIRE HOSE CABINET
FIN	FINISH
FLR, FL	FLOOR
ga	GAUGE
Galv	GALVANIZED
GLUM	GALVALUME
G.C	GENERAL CONTRACTOR
G.L	GRID LINE
GWB	GYPSUM WALL BOARD
H.W	HAZARDOUS WASTE
H	HIGH
H.D	HEAVY DUTY
HT	HEIGHT
H.M	HOLLOW METAL
HOR, HORIZ	HORIZONTAL
HR	HOUR
HSS	HOLLOW STEEL SECTION
HYDR	HYDRAULIC
I.D	INSIDE DIAMETER
I/F	INSIDE FACE
INT	INTERIOR
INSUL	INSULATION
L.W	LIGHT WEIGHT
L	LONG
LOC	LOCATION
MAS	MASONRY
MAX	MAXIMUM
MECH	MECHANICAL
MIN	MINIMUM
MISC	MISCELLANEOUS
M.O.	MASONRY OPENING
MR	MIRROR
MTL	METAL
N.I.C	NOT IN CONTRACT
0.C	ON CENTER
0.D	OUTSIDE DIAMETER
O/F	OUTSIDE FACE
O.H	OVERHEAD
OPNG	OPENING
O.W.S.J	OPEN WEB STEEL JOIST
PL	PLATE
P.LAM	PLASTIC LAMINATE
PLYW	PLYWOOD
PNL	PANEL
PREFIN	PREFINISHED
PS	PRESSED STEEL
PTD, PT	PAINTED, PAINT
R/CONC	REINFORCED CONCRETE
R.D.	ROOF DRAIN
REINF	REINFORCED
RM	ROOM
R.O. SHWR	ROUGH OPENING
SIM	SHOWER SIMILAR
SLP	SLOPE
SPEC'D	SPECIFIED
S.S ST, STL	STAINLESS STEEL
STO, STOR	STEEL STORAGE
STRUC	STRUCTURAL
SURF MTD	SURFACE MOUNTED
SUSP	SUSPENDED
TH	THICK / THICKNESS
Т.О.	TOP OF
T.O.C.	TOP OF CONCRETE
TYP	TYPICAL
U/F	UNDER FLOOR
U/G	UNDER GROUND
U/S	UNDER SIDE
V.B	VAPOUR BARRIER
VEH	VEHICLE
VERT	VERTICAL
VEST	VESTIBULE
W	WIDE
W/	WITH
W.MEM	WATERPROOFED MEMBRANE
W.T.	WEEPING TILE









- ARCHITECTURAL
- A0.1 TITLE SHEET, KEY PLAN
- A1.1 DEMOLITION PLAN & REFLECTED CEILING PLAN
- A1.2 BOILER ROOM PLAN & REFLECTED CEILING PLAN
- A2.1 RENOVATION PLAN & REFLECTED CEILING PLAN A2.2 FLOOR SLOPE PLAN & FINISHES PLAN & SCHEDULES
- A3.1 INTERIOR ELEVATIONS

STRUCTURAL

A3.2 DETAILS

S1.1 GENERAL NOTES, PARTIAL FLOOR PLANS, AND SECTION

MECHANICAL **MP2.1 MAIN FLOOR - PLUMBING DEMOLITION PLAN** MP2.2 MAIN FLOOR - PLUMBING RENOVATION PLAN MF2.1 MAIN FLOOR - FIRE PROTECTION PLAN MY2.1 MAIN FLOOR - HYDRONIC RENOVATION PLAN MH2.1 MAIN FLOOR - HVAC DEMOLITION PLAN MH2.2 MAIN FLOOR - HVAC RENOVATION PLAN

ELECTRICAL E0.1 ELECTRICAL SYMBOLS AND ABBREVIATIONS E2.5 ELECTRICAL LAYOUTS - UNIVERSAL CHANGE ROOM

#### SCOPE OF WORK

THE SCOPE OF WORK FOR THE INTERIOR RENOVATIONS TO THE PAN AM POOL CONSISTS OF RENOVATIONS AND RE-CONFIGURATION TO THE EXISTING UNIVERSAL WASHROOMS AREA. THE RENOVATION DOES NOT REDUCE THE OVERALL WATER CLOSET OR LAVATORY COUNT.

#### HAZARDOUS MATERIALS

THIS BUILDING CONTAINS ASBESTOS CONTAINING MATERIALS.

PRIOR TO THE COMMENCMENT OF THE GENERAL CONTRACTOR BEING ON SITE, AN ASBESTOS ABATEMENT CONTRACTOR WILL REMOVE ANY KNOWN ASBESTOS CONTAINING MATERIALS AND/OR MOLD IN THE SCOPE OF WORK AREA.

IF ASBESTOS OR OTHER HAZARDOUS MATERIALS ARE ENCOUNTERED DURING THE WORK OF THE CONTRACT, THE CONTRACTOR SHALL STOP ALL WORK AND NOTIFY THE CONTRACT ADMINISTRATOR IMMEDIATELY.

#### CODE ANALYSIS

THE SCOPE OF THIS RENOVATION DOES NOT CHANGE THE USE, OCCUPANT LOAD OR MAJOR OCCUPANCY CLASSIFICATION. IN OUR PROFESSIONAL OPINION, LIFE SAFETY

- WILL NOT BE AFFECTED BY THIS MODERNIZATION AND INTERIOR ALTERATION.
- ALL PENETRATIONS IN RATED ASSEMBLIES ARE TO RECEIVE FIRE STOPPING AND/OR DAMPERS TO MAINTAIN RATINGS. REFER TO DRAWINGS AND SPECIFICATIONS.

FLOORS = 1 HR FRR WALLS = AS NOTED ON DRAWINGS

#### CODE ANALYSIS

CONTRACT ADMINISTRATOR WILL APPLY FOR AND PAY FOR THE BUILDING PERMIT. ONCE GENERAL CONTRACTOR IS AWARDED THE PROJECT, THE PERMIT WILL BE TRANSFERRED TO THE GENERAL CONTRACTORS NAME. CONTRACTOR TO APPLY FOR AND PAY FOR ALL OTHER PERMITS REQUIRED FOR THE PROJECT.

### **GENERAL DRAWING NOTES**

THE DRAWINGS SHALL NOT BE SCALED. FOLLOW GIVEN DIMENSIONS ONLY.

THE CONTRACTOR SHALL SATISFY THEMSELVES THAT ALL DIMENSIONS, ELEVATIONS, DATUMS, AND INFORMATION SHOWN ARE CORRECT. VERIFY ALL DIMENSIONS ON SITE. DIMENSIONS ARE AS FOLLOW UNLESS OTHERWISE NOTED: - FACE OF MASONRY WALLS

- EXTERIOR FACE OF ALL INTERIOR WALLS PRIOR TO COMMENCEMENT OF WORK, REPORT ANY DISCREPANCIES TO THE CONTRACT

ADMINISTRATOR. VARIATIONS AND MODIFICATIONS TO WORK SHOWN WILL NOT BE ALLOWED WITHOUT THE WRITTEN PERMISSION OF THE CONTRACT ADMINISTRATOR.

ALL DIMENSIONS ARE IMPERIAL UNLESS OTHERWISE NOTED.

NO REPRODUCTION OF THE DRAWINGS MAY BE MADE WITHOUT THE WRITTEN CONSENT OF THE CITY OF WINNIPEG AND ALL REPRODUCTION MUST BEAR THE NAME OF THE ARCHITECT.

GENERAL CONTRACTOR SHALL NOTIFY THE CONTRACT ADMINISTRATOR OF ANY MECHANICAL AND ELECTRICAL APPARATUS APPEARANCE WHICH MAY VARY FROM THAT INDICATED IN THE CONTRACT DOCUMENTS.

# PAN AM POOL UNIVERSAL CHANGE ROOM

BID OPPORTUNITY #878-2021 25 POSEIDON BAY, WINNIPEG, MANITOBA **ISSUED FOR CONSTRUCTION - APRIL 26, 2022** 



SITE PLAN NOT TO SCALE