

ASSET NUMBER	STREET	LOCATION DESCRIPTION	FLOW TYPE	WORK TYPE NAME	EST COST	COMMENTS	HEIGHT	WIDTH	SEWER LENGTH	START REPAIR	END REPAIR
S-MA50018054	ARCHIBALD ST W OF CL	NODE N OF MH 50012170 TO 1ST MH N OF MISSION ST	CS	FULL SEGMENT LINER	\$162,700	WILL NEED TO TEMPORAEILY REMOVE RESTRICTION AT SOUTH (D/S) MH IN ORDER TO FACILITATE LINER INSTALL -- SEE VIDEO FROM 2016 FOR RESTRICTION. FSL WAS ORIGINALLY ASSIGNED TO 2017 CSP AND WAS NOT COMPLETED. ASSIGNED IT TO	600	600	195.6	0.0	193.8
S-MA60004428	BOWER BV	1ST MH N OF MOUNTBATTERN AV TO 2ND MH N OF MOUNT	LDS	FULL SEGMENT LINER	\$96,300	CROSSBORE PIPE	750	750	96.4	0.0	96.3
S-MA40006736	BRAZIER ST	MH AT GREENE AV TO MH AT LINDEN AV	CS	FULL SEGMENT LINER	\$117,500		900	900	80.1	0.0	79.5
S-MA20011968	CECIL ST()	MH AT ROY AV TO MH AT PACIFIC AV.W.	CS	FULL SEGMENT LINER	\$44,100		750	750	38.0	0.0	38.0
S-MA20016628	COLONY ST	MH @ BALMORAL ST TO 1ST MH N OF PORTAGE AV	CS	FULL SEGMENT LINER	\$157,500	MB, IMAGES AVAIL.	800	1200	137.8	0.0	134.4
S-MA40012891	DAY ST	1ST MH S OF THOM AV TO 1ST MH S OF MCMEANS AV	LDS	FULL SEGMENT LINER	\$179,000		750	750	169.7	0.0	169.7
S-MA50004057	GAUVIN ST	1ST MH S OF CONISTON ST TO 2ND MH S OF CONISTON ST	CS	FULL SEGMENT LINER	\$50,200	FL THROUGHOUT - H @ INVERSE W/ MH 8667 - IMAGES AVAILABLE	600	600	61.0	0.0	60.7
S-MA50007514	HILL ST.	MH AT NIVERVILLE ST TO 1ST MH S OF NIVERVILLE ST	CS	AUGMENTED FS LINER	\$46,000	epr 75.3-79m	600	600	93.5	0.0	92.4
S-MA50015297	LANE N OF ST MICHAEL RD	3RD MH N OF PULBERRY ST TO MH AT ST MARYS RD	LDS	TRENCHLESS PT REPAIR	\$14,000	B, FM -- TRENCHLES POINT REPAIR ONLY REQUIRED HOWEVER MAY BE TO ADDRESSED WITH FSL IF TPR CAN'T BE DONE -- PWD STREET RENEWAL IN 2021	600	600	51.7	0.2	3.0
S-MA20008920	PORTAGE AV	1ST MH E OF KING EDWARD ST TO MH AT GARDEN RD	WWS	FULL SEGMENT LINER	\$195,750	FC, FL, CC, SAM, SAP, SSC	900	900	142.1	0.0	134.8
S-MA20011451	PORTAGE AV(SPL)	1ST MH E OF TYLERHURST ST TO 1ST MH E OF ST. JOHN AMBULANCE WAY	WWS	FULL SEGMENT LINER	\$203,850		900	900	143.0	0.0	140.6
S-MA20009893	SARGENT AV CL	MH AT DUNDAS ST TO TE AT MILT STEGAL DR	CS	FULL SEGMENT LINER	\$105,800	PWD STREET RENEWAL IN 2021	750	750	87.7	0.0	87.7
					\$1,372,700						