



KEY PLAN  
SCALE: N.T.S.

**NOTES:**

THESE DRAWINGS SHALL NOT BE SCALED.

THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.

THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.

ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULIC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.

ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.

WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.

WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.

**KEYNOTES:**

1 REPLACE TYPE 'A' LUMINAIRES SHOWN WITH NEW LED LUMINAIRES.

2 REPLACE TYPE 'D' LUMINAIRES SHOWN WITH NEW LED LUMINAIRES.

**GENERAL NOTES:**

1. THE EC SHALL REUSE THE EXISTING LIGHTING CIRCUITS FOR THE NEW LUMINAIRES AND MAINTAIN EXISTING NIGHT LIGHTING CIRCUITS. NIGHT LIGHT CIRCUITS SHOWN ARE BASED ON AS-BUILTS AND HAVE NOT BEEN FIELD VERIFIED. CONTRACTOR TO IDENTIFY NIGHT LIGHT CIRCUITS ON AS-BUILTS.

2. THE EC SHALL ALLOW FOR THE TEMPORARY REMOVAL OF THE EXISTING 5X5' OPEN CEILING GRID IF REQUIRED FOR THE DEMOLITION OR INSTALLATION SCOPE OF WORK.



No.	REVISION/DESCRIPTION	BY	DATE
1	RE-ISSUED FOR CONSTRUCTION	CLS	22.02.16
0	ISSUED FOR CONSTRUCTION	CLS	22.01.04

DRAWN	RAH	CHECKED	DAL	DESIGNED	CLS	APPROVED
DATE	2021.09.08	USER				
APPROVAL						

CITY OF WINNIPEG  
ASSETS & PROJECT MANAGEMENT  
DEPARTMENT  
MUNICIPAL ACCOMMODATIONS DIVISION  
4TH FLOOR, 185 KING STREET  
WINNIPEG, MANITOBA R3B 1J1

PROJECT  
TENDER 139-2022  
INTERIOR RENOVATIONS FOR  
MILLENNIUM LIBRARY  
251 DONALD ST., WINNIPEG, MB

SHEET TITLE  
MAIN FLOOR  
LIGHTING PLAN

SCALE	PROJECT No:	SHEET No:
3/32" = 1'-0"	21-0107-014	E2

MAIN FLOOR - LIGHTING PLAN  
SCALE: 3/32"=1'-0"

