

1 B0004 B0007 BUILDING SECTION
SCALE: 1:50



2 B0004 B0007 SECTION DETAIL
SCALE: 1:50

NOTE:
1. DEMOLISH EXISTING HAND & GUARD RAILS, RETAIN EXISTING LANDING AND STAIRS, GRATING AND MISC. METALS.
2. PROVIDE NEW STEEL HAND & GUARD RAILS (32mm Ø) AND PAINT.
3. PROVIDE NEW 125mm (5") KICK PLATE BAR AND PAINT.

TACHE BOOST PUMPING STATION REPAIR LEGEND	
KEYNOTE REMEDIATION ACTION	
1	REPOINT MORTAR JOINTS AS REQUIRED ON CHIMINEY, AND INSTALL NEW ALUMINUM CHIMNEY CAP. REFER TO BUILDING ELEVATIONS.
5	REPLACE EXISTING GUARD AND STAIR RAILING TO CURRENT CODE
8	REPOINT MORTAR JOINTS ON GLASS BLOCKS BOTH EXTERIOR AND INTERIOR AS REQUIRED THROUGHOUT
9	REPLACE BROKEN GLASS BLOCKS AS REQUIRED THROUGHOUT



3 B0007 B0007 SECTION DETAIL
SCALE: 1:10

0 1250 2500 mm

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
AECOM Canada Ltd.
No. 4671 Date: 2022/10/11

NO.	REVISIONS	DATE	DESIGN	CHECK
0	ISSUED FOR CONSTRUCTION	2022-10-11	KS	MH

AECOM

DESIGNED BY: K. SIDDALL	CHECKED BY: M. HOQUE
DRAWN BY: G. PROFETA	APPROVED BY:
SCALE:	RELEASED FOR CONSTRUCTION BY:
DATE: 2022-10-11	DATE:
CONSULTANT NO.: 60661011	

ENGINEER'S SEAL
PROVINCE OF MANITOBA
Oct. 11,2022
JOHN D'IGNAZIO
REGISTERED ARCHITECT

Winnipeg
THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

TACHE BOOSTER PUMPING STATION
AND SURGE TOWER UPGRADES
ARCHITECTURAL
TACHE BOOSTER PUMPING STATION REMEDIATION
BUILDING SECTION

CITY DRAWING NUMBER	SHEET	REV.	SIZE
1-0660M-B0007-001	6 of 13	0	A1

LAST SAVE: 2022/10/11 6:54 AM
PATH: L:\Legacy\CAWPS\FP001\Data\Projects\60661011\900-CAD_GIS\910-CAD\20-SHEETS\Architectural CAD June 15 2022\A0006.dwg