





ALL WORK AND MATERIALS TO BE IN ACCORDANCE WITH THE LATEST REVISION OF THE CITY OF WINNIPEG

STANDARD CONSTRUCTION SPECIFICATIONS. CONTRACTOR TO CONFIRM THE LOCATION OF ALL UTILITIES/SERVICES IN THE FIELD PRIOR TO CONSTRUCTION.

RENEW CURB, SPLASH STRIP, BULLNOSE, AND SIDEWALK AS IDENTIFIED BY CONTRACT ADMINISTRATOR.

ALL PRIVATE WALKWAYS TO BE ADJUSTED TO NEW SIDEWALK OR TOP OF CURB ELEVATION, AS REQUIRED.

ADJUST OF PRIVATE OF THE CONSTRUCTION OF ADDITIONAL PRIVATE P MODIFIED BARRIER CURB TO BE CONSTRUCTED AT ALL INTERSECTION RADII AND BACK LANE RADII.

LAMP STANDARDS, HYDRO POLES, AND ANCHORS THAT REQUIRE TEMPORARY SUPPORT, REMOVAL OR REPLACEMENT, TO BE DONE SO AT THE EXPENSE OF THE CONTRACTOR AS NECESSARY.

CONTRACTORS TO TAKE PRECAUTIONARY STEPS TO PROTECT EXISTING TREES WITHIN THE LIMITS OF CONSTRUCTION FROM DAMAGE FROM CONSTRUCTION ACTIVITIES AS OUTLINED IN THE SPECIFICATIONS.

9. ALL BOULEVARDS TO BE SODDED UNLESS OTHERWISE NOTED.

10. FULL AND PARTIAL DEPTH JOINT REPAIRS, AND SLAB RENEWALS TO BE FINALIZED IN THE FIELD PRIOR TO

CONSTRUCTION. THE REPAIRS IDENTIFIED ON THIS DRAWING ARE FOR TENDER PURPOSE ONLY.

11. ALL JOINTS AND CRACKS TO BE SEALED AFTER DIAMOND GRINDING IS COMPLETED.

12. DIAMOND GRINDING LIMITS TO BE FINALIZED IN THE FIELD PRIOR TO CONSTRUCTION, AS DIRECTED BY

	TRANSIT STOP	EDGE OF SIDEWALK			
₽	HYDRO POLE	FENCE		FENCE	
0	MANHOLE	PROPERTY LINE			
	CATCH BASIN			EDGE OF CONCRETE & ASPHALT	
Δ	CURB INLET			SIDEWALK RENEWAL	
-	HYDRANT			DIAMOND GRINDING LIMITS	
\otimes	VALVE			FULL DEPTH REPAIRS	
3	CURB STOP			ASPHALT RENEWAL	***************************************
\longrightarrow	ANCHOR			CONCRETE PRESERVATION	
# 111	CIVIC ADDRESS			BOULEVARD GRADING	(////////
EXISTING	LEGEND-PLAN	PROPOSED	EXISTING	LEGEND-PLAN	PROPOSED

WHOLE NUMBERS INDICATE MILLIMETRES DECIMALIZED NUMBERS INDICATE METRES ENGINEERS GEOSCIENTISTS

PRELIMINARY

MANITOBA Certificate of Authorization WSP Canada Inc. NOT FOR CONSTRUCTION No. 5750

G.B.M. N/A ELEV				115[)		WSP Canada Inc. 1600 Buffalo Place Winnipeg, MB R3T 6B8 t. 204.477.6650		ENGINEER'S SEAL OF MANIFORM OF THE SEAL	
H							f. 204.474.2864 www.wsp.com] / J.S.F. \ \	
F				DESIGNED BY	JM	CHECKED BY	SS	MAGNE MEMBER 31236	
E									
D				DRAWN BY	SB	APPROVED BY	VM	PROFESSIONAL	
С								The state of the s	
В	ISSUED FOR TENDER	R TENDER 04/22/22 JM		HOR. SCALE 1:500		RELEASED FOR — CONSTRUCTION		CONSULTANT ACAD DWG. NO.	
Α	ISSUED FOR DETAIL DESIGN REVIEW	04/19/22	JM	VERTICAL	N/A	CONSTRUCTION			
NO.	REVISIONS	DATE	BY	DATE	03/24/2022	DATE	-	221-02142-00-13	



THE CITY OF WINNIPEG PUBLIC WORKS DEPARTMENT ENGINEERING SERVICES DIVISION

2022 STREETS MAINTENANCE PRESERVATION PROGRAM MORAY STREET NORTH BOUND

CONCRETE PRESERVATION AND DIAMOND GRINING

WILLIAM CLEMENT BRIDGE TO PORTAGE AVENUE

N/A 13 OF 13 TENDER NO. 199-2022

METRIC