

SEWER JUNCTION INFORMATION FROM SEWER VIDEO INSPECTION		
SEWER ID S-MA20015377		
DISTANCE FROM MH2013884		
DISTANCE	DIAMETER	CLOCK
4.2	200	7:00
4.2	150	10:00
9.4	150	10:00
19.6	150	10:00
19.6	150	11:00
19.6	150	2:00
23.9	150	12:00
27.3	150	10:00
27.3	150	2:00
35.6	150	10:00
35.6	150	1:00
35.6	150	2:00
42.8	150	10:00
42.8	150	2:00
49.6	150	10:00
49.6	150	2:00
49.8	150	11:00
57.4	150	10:00
57.4	150	2:00
64.7	150	10:00
64.7	150	2:00
66.1	200	10:00
66.1	200	2:00
72.4	150	10:00
72.4	150	2:00
79.0	150	11:00
80.5	150	11:00
80.5	150	2:00
83.4	150	2:00
88.0	150	10:00
88.0	150	2:00
95.6	150	10:00
95.6	150	2:00
103.3	150	10:00
103.3	150	2:00
110.6	150	10:00
110.6	150	2:00
118.8	150	10:00
118.8	150	2:00
126.0	150	10:00
126.0	150	2:00



WALNUT STREET



REMOVE AND REPLACE TOP 0.9m CONC. RISERS BELOW FRAME w/750 PRECAST CONC. RISERS.

REMOVE AND REPLACE TOP 0.3m BRICK RISERS BELOW FRAME w/750 PRECAST CONC. RISERS.

S-MH20013884  
RIM 232.440  
INV W 225.310  
INV E 225.310

S-MH20013863  
RIM 232.510  
INV N 225.110  
INV S 225.110

127.8 OF 1200x1550 CONC CS TO BE LINED  
S-MA20015377  
(FULLY DETERIORATED)

**WARNING**

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

- 1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.
- 2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 140/92 FOR DETAILS



Certificate of Authorization  
Stantec Consulting Ltd.

No. 1301

**METRIC**

WHOLE NUMBERS INDICATE MILLIMETRES  
DECIMALIZED NUMBERS INDICATE METRES



TENDER NO. 212-2022

FOR INDEX SEE  
13042

LOCATION APPROVED UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE DATE

NOTE:  
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. ELEV.	NO.	REVISIONS	DATE	BY
	2	ISSUED FOR TENDER	22.05.06	RS
	1	ISSUED FOR REVIEW	22.04.29	RS



DESIGNED BY	RS	CHECKED BY	RS
DRAWN BY	OS	APPROVED BY	RS
HOR. SCALE:	1:750	RELEASED FOR CONSTRUCTION:	SC
VERTICAL:		DATE	22.05.04
DATE	22.03.15		

ENGINEER'S SEAL  
  
CONSULTANT DRAWING NO.  
**C-102**



2022 SEWER RENEWALS BY CIPP LINING (LARGE DIAMETER)  
CONTRACT 3  
**WALNUT STREET**  
MH AT PRESTON AVE  
TO MH AT PURCELL AVE

SHEET	OF
<b>04</b>	<b>12</b>
CAD FILE DRAWING NUMBER <b>20592c-101.dwg</b>	
CITY DRAWING NUMBER <b>13044</b>	

V:\112\active\1120592\0300\_drawing\0302\_sheet\_files\02\_civil\20592c-101.dwg