

DRAWING INDEX

SHEET NUMBER	CITY OF WINNIPEG DRAWING NUMBER	DRAWING TITLE
1	D-16333	COVER PAGE
2	D-16334	DRAWING INDEX, DESIGN NOTES, LEGEND, & ABBREVIATIONS
3	D-16335	SASKATCHEWAN AVENUE – 40m EAST OF EMPRESS STREET TO 105m EAST
4	D-16336	SASKATCHEWAN AVENUE – 105m EAST OF EMPRESS STREET TO 210m EAST
5	D-16337	SASKATCHEWAN AVENUE – 65m WEST OF MIDLAND STREET TO MIDLAND STREET
6	D-16338	MIDLAND STREET – SASKATCHEWAN AVENUE TO 60m NORTH
7	D-16339	MIDLAND STREET – 60m NORTH OF SASKATCHEWAN AVENUE TO 145m NORTH
8	D-16340	WHITEGATES CRESCENT – BROWNING BOULEVARD TO REYNOLDS BAY NORTH LEG
9	D-16341	REYNOLDS BAY NORTH LEG – WHITEGATES CRESCENT TO REYNOLDS BAY EAST LEG
10	D-16342	VOYAGER AVENUE – CAVALIER DRIVE TO BISSETT CRESCENT
11	D-16343	QUAIL RIDGE ROAD (EAST LEG) – QUAIL RIDGE ROAD (SOUTH LEG) TO 85m NORTH
12	D-16344	QUAIL RIDGE ROAD (EAST LEG) – 85m NORTH OF QUAIL RIDGE ROAD (SOUTH LEG) TO 175m NORTH

ABBREVIATIONS

WWS	WASTE WATER SEWER
CS	COMBINED SEWER
LDS	LAND DRAINAGE SEWER
ℙ	PROPERTY LINE
℄	CENTER LINE
G.I.S.	GEOGRAPHIC INFORMATION SYSTEM
B.M.	BENCH MARK
TH	TEST HOLE
ELEV	ELEVATION
INV	INVERT
MIN	MINIMUM
MAX	MAXIMUM
SL	STREET LIGHTING
TS	TRAFFIC SIGNALS
ABAND	ABANDONED
BLDG	BUILDING
HSE	HOUSE
CRN	CORNER
OPP	OPPOSITE
C/S OR S/C	CURB STOP
MTS	MANITOBA TELEPHONE SYSTEM
R.O.W.	RIGHT-OF-WAY
WM	WATERMAIN
CULV	CULVERT
MH	MANHOLE
CB	CATCH BASIN
CI	CURB INLET
VERT.	VERTICAL
HORZ.	HORIZONTAL
I.B.	IRON BAR
FIBRE	FIBRE OPTIC
TYP	TYPICAL
X-ING	CROSSING
HYD	HYDRANT
EX	EXISTING
N	NORTH
E	EAST
S	SOUTH
W	WEST
W/	WITH
C/W	CONSTRUCTED WITH
CONC	CONCRETE
AC	ASBESTOS CEMENT
VC OR CLAY	VITRIFIED CLAY
CI	CAST IRON
DI	DUCTILE IRON
PVC	POLYVINYL CHLORIDE
HDPE	HIGH DENSITY POLYETHYLENE
PCCP	PRESTRESSED CONCRETE CYLINDER PIPE

LEGEND

DESCRIPTION	PLAN VIEW	
	EXISTING	PROPOSED
WATER PIPE		
FIRE HYDRANT		
VALVE		
CURB STOP		
REDUCER		
COUPLING OR SLIDDER		
CROSS		
BEND – 11.25°, 22.5°, 45°, 90°		
TEE		
VERTICAL BEND		
ANODE		
REPAIR MARKER		
PLUG		
SEWER PIPE		
MANHOLE		
CATCH BASIN		
CURB INLET		
JUNCTION		
℄ DITCH		
CULVERT		
SURVEY BAR		
SURVEY MONUMENT		
TREE – DECIDUOUS		
TREE – CONIFEROUS		
HYDRO		
HYDRO POLE		
BOLLARD		
LAMP STANDARD		
HYDRO POLE W/STREET LIGHTING		
POLE		
FLAG/BANNER POLE		
GUY ANCHOR		
M.T.S. POLE		
PEDESTAL OR BOX		
CABINET		
M.T.S., SHAW, OR VIDEON		
TRAFFIC SIGNALS		
TRAFFIC LIGHT STANDARD		
GAS		
STEAM		
FIBRE OPTIC		
FENCE		
EDGE OF PAVEMENT OR GUTTER		
EDGE UNPAVED OR GRAVEL ROAD		
℄		
PROJECTED ℄		
LOT LINE		
SIDEWALK – PATHWAY		
EASEMENT		
EDGE OF BUILDING		
MAILBOX		
PARKING METER		
MTS PEDESTAL		
TEST HOLE		
TREE LINE OR BUSH		

DESCRIPTION	PROFILE	
	EXISTING	PROPOSED
WATER PIPE		
HYDRANT TOP		
VALVE		
TEE OR CROSS		
COUPLING OR BEND		
REDUCER		
END OF PIPE		
SEWER PIPE		
UNPAVED GROUND SURFACE		
PAVED GROUND SURFACE – ℄ PIPE		
GUTTER (NORTH AND WEST)		
GUTTER (SOUTH AND EAST)		
℄ DITCH (NORTH AND WEST)		
℄ DITCH (SOUTH AND EAST)		
STRUCTURE		
MANHOLE OR CATCH BASIN		

CONSTRUCTION NOTES

1. EXPOSE EXISTING WATERMAIN & CONFIRM INVERTS PRIOR TO CONSTRUCTION.
2. LOCATION OF ALL SERVICES TO BE CONFIRMED IN THE FIELD.
3. INSTALL WATERMAIN BY TRENCHLESS METHODS.
4. TRENCHES AND EXCAVATIONS WITHIN 1 METRE OF A PAVED AREA INCLUDING SIDEWALKS SHALL BE CLASS 3 BACKFILL.
5. ALL MATERIALS SHALL CONFORM TO THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
6. MINIMUM COVER TO TOP OF WATERMAIN SHALL BE 2.4 m.
7. REPLACE ALL EXISTING LEAD OR POLYBUTYLENE SERVICES FROM PROPOSED WATERMAIN TO ℄.
8. NOTIFY ALL AFFECTED RESIDENTS AND BUSINESSES 24 HOURS IN ADVANCE OF ANY WATER SHUTDOWNS OR DISRUPTION OF SERVICE.
9. EXPOSE ALL EXISTING UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION TO CONFIRM DEPTHS. ANY CONFLICTS WITH PROPOSED WATERMANS AND EXISTING UNDERGROUND UTILITIES SHALL BE REPORTED TO THE CONTRACT ADMINISTRATOR PRIOR TO INSTALLATION.

HATCH PATTERNS

EXISTING	PROPOSED	DESCRIPTION
		EARTH OR GROUND ABOVE PIPE
		SAND OR OTHER FINE MATERIAL
		CONCRETE
		WASHED STONE OR GRANULAR MATERIAL
		INTERLOCKING STONE
		METAL
		GRAVEL OR STONE



LOCATION APPROVED UNDERGROUND STRUCTURES		DESIGNED BY		CHECKED BY		ENGINEER'S SEAL	
SUPV. U/G STRUCTURES COMMITTEE	DATE	–		IJM			
NOTE:	LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.	DRAWN BY	NL	APPROVED BY	IMJ		
		SCALE:	HORIZONTAL N/A	RELEASED FOR CONSTRUCTION			
			VERTICAL				
0	ISSUED FOR TENDER	22/05/25	IJM				
NO.	REVISIONS	DATE	BY	DATE	2022 05 25		

THE CITY OF WINNIPEG
 WATER AND WASTE DEPARTMENT
 ENGINEERING DIVISION

2022 WATERMAIN RENEWALS
 CONTRACT 10
 INDEX PAGE

CONSULTANT DRAWING NUMBER: 2200120200-DWG-C0002

CITY DRAWING NUMBER: D-16334

SHEET 2 OF 12