

	234.0
	232.0
·	230.0
	228.0
3	226.0
	224.0
12° ND REMO	
1+252.49 300 GV	<ol> <li>FLUSHING AND OTHER WATER COLLECTED DURING THE COURSE OF THE WORK MAY BE DISCHARGED INTO THE MANHOLES SHOWN ON THE DRAWINGS AT THE MAXIMUM FLOW RATED IDENTIFIED, TO AN LDS SEWER (WITH DECHLORINATION), OR TO THE RIVER (WITH DECHLORINATION AND ASSOCIATED PROVISIONS) IN ACCORDANCE WITH THE SPECIFICATIONS.</li> <li>THE FEEDER MAIN MAY BE DEWATERED TO FACILITATE CONSTRUCTION.</li> <li>CONTRACTOR SHALL ADDRESS ASSESS ACTIVE INFILTRATION INTO THE EXISTING FEEDER MAIN PRIOR TO PIPE DISASSEMBLY, AND BE PREPARED TO PUMP INFILTRATION. SEE SPECIFICATIONS.</li> <li>THE CONTRACTOR SHALL INSTALL A NSF 61, LINER.</li> <li>FFRP LINER TERMINATIONS SHALL BE COMPLETED IN ACCORDANCE WITH THE SPECIFICATIONS AND RECONNECT TO THE EXISTING PIPING IN A MANNER CONSISTENT WITH THE EXISTING PIPING CONFIGURATION. THE CONTRACTOR IS RESPONSIBLE FOR DEVELOPING A FFRP LINER TERMINATION CONFIGURATION WHICH IS COMPATIBLE WITH THE EXISTING PIPING CONFIGURATION AND MEETS THE SPECIFICATIONS.</li> <li>THE CONTRACTOR SHALL COMPLETE THE FOLLOWING POST INSTALLATION:</li> <li>LEAKAGE TEST. LEAKAGE TEST SHALL INCLUDE THE VERTICAL DROP PIPE WITHIN THE WEST TUNNEL SHAFT AS SHOWN. COMPLETION OF A PRELIMINARY LEAKAGE TEST OF THE LINER AND TERMINATIONS PRIOR TO ASSEMBLY OF THE ADJACENT CHAMBER PIPING RECOMMENDED.</li> <li>DISINFECTION AND HEALTH TESTING AFTER ASSEMBLY OF ADJACENT CHAMBER PIPING AS SHOWN AND AS SPECIFIED.</li> <li>RESTORE BOULEVARDS, SIDEWALKS, AND ROADWAYS UPON COMPLETION OF THE WORK.</li> <li>THE CONTRACTOR MAY UTILIZE THE TWO WESTBOUND LANES ON REDWOOD AVE WEST OF THE HARRY LAZARENKO BRIDGE AS A LAY DOWN AREA. BOTH EASTBOUND AND WESTBOUND TRAFFIC MUST BE MAINTAINED AT ALL TIMES EXCEPT AS PERMITTED.</li> <li>THE CONTRACTOR MAY REQUEST A SINGLE 48 HOUR ROAD CLOSURE OF REDWOOD AVE AND HESPELER AVE TO FACILITATE LINER INSTALLATION.</li> </ol>
ON. 782.91 BER, 700 5.03 3.05 95.95 00 100 100 100 100 100 100 100	375 PVC SRS 375 P
NED son 22	Image: Winniped Winniped WinnipedTHE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISIONKILDONAN - REDWOOD FEEDERMAINSHEET 03 OF 04
BER	CROSSING REHABILITATION PLAN / PROFILE RED RIVER N OF HARRY LAZARENKO BRIDGE REDWOOD AVENUE TO HESPELER AVENUE UE PATH: C:\Users\leipnig\AppData\local\temp\AcPublish_19480\

FILE PATH: C:\Users\leippia\AppData\Local\Temp\AcPublish\_19480\ FILE NAME: 60622949-SHT-30-0000-C-1001.dwg