

ASSET NUMBER	STREET NAME	LOCATION DESCRIPTION	FLOW TYPE	WORK NAME TYPE	EST COST	COMMENTS	DIAMETER	LENGTH
S-MA00009951	ANDREWS ST	MH @ ATLANTIC AV TO TE @ BACKLANE S ATLANTIC AV	LDS	AUGMENTED FS LINER	\$33,400	Install MH at back lane for lining purposes and an EPR is required from 28.6m upstream to the new installed MH	300	41.83
S-MA20017405	ARLINGTON AV	3RD MH S OF SARGENT AV TO MH AT ELLICE AV (NPL)	CS	FULL SEGMENT LINER	\$34,400	B, FM, FC, CC, CL, CM	375	83.40
S-MA20017323	ARLINGTON ST	1ST MH S OF ELLICE AV TO 2ND MH S OF ELLICE AV	CS	FULL SEGMENT LINER	\$45,950		300	116.20
S-MA20015032	ARLINGTON ST	1ST MH S OF WESTMINSTER AV TO MH AT WESTMINSTER AV	CS	AUGMENTED FS LINER	\$78,430	HSV, FM, FL, CM, CC, CL, JOM, JAL, SAP, SSS, IDJ. EPR at 111.9-122.8m	450	122.80
S-MA20015297	ARLINGTON ST	2ND MH S OF ST PAUL AV TO MH AT PORTAGE AV	CS	FULL SEGMENT LINER	\$39,850	FL,FC,BAD CONNECTIONS,IMAGES AVAIL.	450	83.90
S-MA20015346	ARLINGTON ST	1ST MH S OF ST MATTHEWS AV TO MH AT ST PAUL AV	CS	FULL SEGMENT LINER	\$55,150	FC, FM, CC, CL	450	117.90
S-MA20011875	BANNATYNE AV W()	MH AT CAMPION ST TO MH AT CECIL ST	CS	FULL SEGMENT LINER	\$30,500		450	68.31
S-MA70044305	DUNDURN PL	1ST MH W OF MARYLAND ST TO MH AT MARYLAND ST	CS	FULL SEGMENT LINER	\$33,000	SEWER PARTIALLY UNDER NEW PAVEMENT IN 2020 PW STREET WORK. SHOULD LINE BEFORE A DIG IS SCHEDULED UNDER NEWER PAVEMENT.	300	79.60
S-MA20009354	ERIN ST	2ND MH N ELLICE AV - 3RD MH N ELLICE AV	CS	FULL SEGMENT LINER	\$43,150		300	109.01
S-MA20010020	ERIN ST	2ND MH S WELLINGTON AV - 3RD MH S WELLINGTON AV	CS	FULL SEGMENT LINER	\$37,900	CL	300	93.31
S-MA20011301	ERIN ST	1ST MH S OF ST MATTHEWS AV-MH@ST MATTHEWS AV	CS	FULL SEGMENT LINER	\$37,550		300	93.11
S-MA20015035	EVANSON ST	1ST MH N OF WOLSELEY AV TO MH AT WESTMINSTER AV	CS	AUGMENTED FS LINER	\$78,430	HSV, FM, FL, CL, JOM, JSM, SSS. POTENTIAL EPR AT 9.1M TO RESOLVE HVV.	450	122.70
S-MA20015364	HOME ST	MH AT PRESTON AV (S.LEG) TO MH AT PRESTON AV (N.LEG)	CS	AUGMENTED FS LINER	\$35,240	Poor condition up to 26.9m (64% of segment); DR 20%, H, B x4, FM, CM LARGE PORTION (27m) MAY BE EPR IF BEYOND CIPP DESIGN LIMITS.	300	41.70
S-MA20017308	HOME ST	2ND MH S OF ELLICE AV TO 3RD MH S OF ELLICE AV	CS	AUGMENTED FS LINER	\$50,800	APPARENT HOLE AT 13M IS CONCRETE; B, BSV, FM, FC, HSV	375	85.40
S-MA20015031	HOME ST(CL)	2ND MH N OF WOLSELEY AV TO MH AT WESTMINSTER AV	CS	AUGMENTED FS LINER	\$78,430	FM, FC, FL, CM, CS, CC, CL. EPRS AT 0-6m and 68.6-70.6m	450	123.00
S-MA00007618	KEEWATIN ST	1ST LDS MH S SELKIRK AV (M) - LDS MH @ SELKIRK AV (M) SPL	LDS	FULL SEGMENT LINER	\$24,250	HOLES IN INVERT -- PWD STREET WORK IN 2021 -- NEED TO REHAB WITH CIPP BEFORE DEFECTS WORSEN	300	54.70
S-MA00000507	LE PERESS AV	MH AT MAIN ST (W.PL) TO TE AT MAIN ST (W.OF CL)	WWS	AUGMENTED FS LINER	\$35,000	EPR@ 12-17m	250	17.00
S-MA20011862	LINCON AV()	1ST MH W OF CECIL ST.TO MH AT CECIL ST	CS	FULL SEGMENT LINER	\$36,850		375	97.31
S-MA20014363	MARYLAND ST	1ST MH N OF PURCELL AV TO MH AT ALLOWAY AV	CS	FULL SEGMENT LINER	\$30,900	DSC, FM, DAE, FC, SSS, CC	300	73.50
S-MA20013686	MIDDLE GT	1ST MH N OF BLANCHARD AV TO 2ND MH N OF BLANCHARD AV	CS	FULL SEGMENT LINER	\$34,700	HVV, FC, FL, FM	375	98.70
S-MA00000416	MURRAY AV(S.OF CL)	1ST MH E OF FROG PLAIN WY TO 1ST MH W OF MAIN ST	WWS	FULL SEGMENT LINER	\$44,200	SAM, SAP, SSC, ISSR	250	111.80
S-MA70051399	MURRAY AV(S.OF CL)	MH AT DANFORD DR TO 1ST MH E OF DANFORD DR	WWS	AUGMENTED FS LINER	\$42,330	FM, FL, CC, CL, SAM, SAP. EPR @ 69.5-72.5m	250	73.00
S-MA00000465	RIDGECREST AV	1ST MH W OF MAIN ST TO 2ND MH W OF MAIN ST	WWS	AUGMENTED FS LINER	\$42,200	EPR @ 70.5-72.5m	250	85.40
S-MA00012620	RUPERTSLAND AV	1ST MH E AIKINS ST TO MH @ AIKINS ST	CS	AUGMENTED FS LINER	\$47,560	EPR @ 8.8-12.7m	300	97.91
S-MA20005946	SHARP BV	1ST MH S OF NESS AV TO 2ND MH S OF NESS AV	CS	FULL SEGMENT LINER	\$35,450	FCJ, Chipped joints, FL, B, D>10% - images available	225	86.81
S-MA00012466	SINCLAIR ST	MH AT BANNERMAN AV TO PLUG N OF BANNERMAN AV	LDS	FULL SEGMENT LINER	\$17,600		300	41.01
S-MA00012467	SINCLAIR ST	1ST MH W.OF KIRBY DR. TO MH AT KIRBY DR.	LDS	FULL SEGMENT LINER	\$13,100		300	13.70
S-MA20017175	ST MATTHEWS AV	MH AT BURNELL ST(EPL) TO MH AT ARLINGTON ST	CS	FULL SEGMENT LINER	\$40,700	FL,H,BAD CONNECTION, IMAGES AVAILABLE	300	101.70
S-MA20015491	TORONTO ST	MH AT PORTAGE AV (NPL) TO MH AT PORTAGE AV (N OF CL)	CS	FULL SEGMENT LINER	\$12,350	FL, FH3, FM, CL	375	21.10
S-MA20009480	WALL ST	1ST MH S OF ELLICE AV TO 2ND MH S OF ELLICE AV	CS	FULL SEGMENT LINER	\$35,100	B, H, FC	300	85.51
S-MA20013976	WALNUT ST	MH AT WOLSELEY AV (CL) TO MH AT WOLSELEY AV (N.PL)	CS	AUGMENTED FS LINER	\$32,020		375	10.90
S-MA20013978	WOLSELEY AV	2ND MH W OF MARYLAND ST TO MH AT WALNUT ST	CS	AUGMENTED FS LINER	\$54,320	H, HSV, BSV, DR 10%, FM, CM, JOM, JSM, SSS; Majority of segment in poor condition. Possible EPR needed at 69.8 - 76.5m	300	111.80
S-MA00000530	WOODBINE AV	2ND MH E.OF DONAN ST TO 3RD MH E.OF DONAN ST.	WWS	AUGMENTED FS LINER	\$55,000	EPR @ 0-3.9m	250	97.40
S-MA00000428	WOODBINE AV	3RD MH W OF DONAN ST TO 2ND MH W OF DONAN ST	WWS	AUGMENTED FS LINER	\$47,370	EPR 56.2-59.3	250	96.00
					\$1,393,180			