

## APPENDIX R – EQUIPMENT LIST SAMPLE

Equipment Tag	Description	Training Required	Lamacoid	Lamacoid Type	Submittals Required	Equipment Quantity	Drawing Number	Specification Section
<b><i>MCPhillips Collection Building (0640B)</i></b>								
CB-PNL-B10	250A 2P Circuit Breaker	No	Yes	D	Yes	1	E0001-001	26 05 53
DP-B701	600V Distribution Panel	No	Yes	A	Yes	1	E0001-001	26 07 80
HMI-G767	Human Machine Interface	Yes	Yes	D	Yes	1	E0013-001	29 08 41
MCC-G766	Motor Control Centre	Yes	Yes	A	Yes	1	E0006-001	26 07 80
CB-G767	125A 3P Circuit Breaker	No	Yes	D	Yes	1	E0006-001	26 07 80
LBD-G767	110kW Load Bank	Yes	Yes	A	Yes	1	E0007-001	26 21 13
<b><i>MCPhillips Main Pumping Station "0640M"</i></b>								
CHLR-M640	Main Pumphouse Air Cooled Chiller	Yes	Yes	A	Yes	1	M009-001	23 82 00
CDR-M640	Air Cooled Condenser	Yes	Yes	A	Yes	1	M009-001	23 82 00
P-M641	Chilled Glycol Circulation Pump - 11.2 kW	Yes	Yes	B	Yes	1	M009-001	23 21 23
P-M642	Chilled Glycol Circulation Pump – 11.2 kW	Yes	Yes	B	Yes	1	M009-001	23 21 23
TNK-M643	Chilled Glycol Expansion Tank	Yes	Yes	B	Yes	1	M009-001	23 82 00
AS-M644	Chilled Glycol Air Separator	No	Yes	B	Yes	1	M009-001	23 82 00
	NEMA 4x Exit Sign	No	No		Yes	4	E0042-002	
<p><b>General Notes:</b></p> <ol style="list-style-type: none"> <li>Not all equipment required for the Work is included I the list herein. This is a partial listing of main equipment only. Refer to the drawings and specifications for all equipment requirements.</li> <li>Include all costs for the supply and complete installation of all equipment herein, and all equipment indicated on the drawings and in the specifications.</li> <li>Include all costs for new lamacoids.</li> <li>Include all costs for training.</li> <li>Notwithstanding C2.4, in the event of discrepancies between this list and the drawings or specifications, the most onerous and costly option shall take precedence prior to clarification by the Contract Administrator.</li> <li>Equipment quantities indicated include required spare components.</li> </ol>								