| SEWER JUNCTION INFORMATION FROM SEWER VIDEO INSPECTION | | | |
|---|---|---|---|
| SEWER ID S-MA50007515 | | | |
| Reference MH | Distance | DIA | Clock |
| S-MH50006439 | 004.4 | 150 | 02 |
| - | 005.1 | 150 | 10 |
| - | 014.3 | 150 | 10 |
| - | 018.0 | 150 | 02 |
| - | 024.0 | 150 | 11 |
| - | 028.4 | 150 | 01 |
| - | 031.2 | 150 | 01 |
| - | 034.8 | 150 | 11 |
| - | 038.4 | 150 | 12 |
| - | 047.3 | 150 | 01 |
| - | 050.7 | 150 | 11 |
| - | 061.9 | 150 | 02 |
| - | 065.6 | 150 | 11 |
| - | 072.2 | 150 | 11 |
| - | 080.2 | 150 | 01 |

**Traffic Controls**

Regional Street Lane Closure Required: No

Impacted Regional St: N/A

**General Requirements:**

Residential Street Restrictions

ENGINEERS GEOSCIENTISTS MANITOBA

Certificate of Authorization

AECOM Canada Ltd.

No. 4671 Date: 23/09/06

**WARNING**

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT, THE CONTRACTOR MUST:
1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.
2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.
SEE PROVINCIAL REGULATION 140/92 FOR DETAILS

FOR INDEX SEE 13362

METRIC

WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

0 2.5 5 10 15 20 Metres

AECOM REVIEW | DRFT CHK

FILE NAME: Saved By:

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPR. U/G STRUCTURES COMMITTEE DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

| NO. | REVISIONS | YY/MM/DD | BY |
|---|---|---|---|
| 0 | ISSUED FOR TENDER | 23/09/06 | ES |

AECOM

| | | | |
|---|---|---|---|
| DESIGNED BY | TB | CHECKED BY | CM |
| DRAWN BY | ES | APPROVED BY | CM |
| HOR. SCALE | 1:750 | RELEASED FOR CONSTRUCTION | |
| VERT. SCALE | N/A | | |
| DATE | | DATE | 23-09-14 |

PROFESSIONAL'S SEAL

PROVINCE OF MANITOBA
T. J. BEAVIS
Member
38263
2023-09-19
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT DRAWING NO.

Winnipeg

# THE CITY OF WINNIPEG
## WATER AND WASTE DEPARTMENT

**2023 SEWER RENEWALS BY CIPP LINING**
**CONTRACT 5**
**S-MA50007515**
**HILL STREET**

HILL ST 1ST MH S OF NIVERVILLE AVE TO MH AT CATON ST

SHEET 7 OF 15

CITY DRAWING NUMBER **13367** REV 0

PLOT DATE:

TENDER No. 599-2023
CONTRACT NUMBER:

FILE PATH:
FILE NAME: 60703129_2023_r0.mxd