SEWER JUNCTION INFORMATION FROM SEWER VIDEO INSPECTION			
SEWER ID S-MA20016571			
Reference MH	Distance	DIA	Clock
S-MH20014905	016.0	250	12
-	029.4	250	12
-	054.5	300	11
-	056.4	250	12
-	057.0	250	12
-	069.7	250	12
-	082.4	250	12
-	085.9	250	11
-	088.7	150	11
-	095.2	250	12

ENGINEERS GEOSCIENTISTS MANITOBA

Certificate of Authorization

AECOM Canada Ltd.

No. 4671 Date: 23/09/06

WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT, THE CONTRACTOR MUST:
1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.
2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.
SEE PROVINCIAL REGULATION 140/92 FOR DETAILS

Traffic Controls

Regional Street Lane Closure Required: Yes
Impacted Regional St: Portage Ave, Colony St., Memorial Blvd, Vaughan St.

General Requirements:

Maintain two lanes of traffic in each direction of Portage Ave. Maintain minimum one lane of traffic in each direction on Colony St./Memorial Ave.
Maintain minimum 1 lane of traffic in each direction on Vaughan St. Maintain all turn movements at the intersection of Portage Ave. and Colony St./Memorial Ave. Maintain all turn movements at the intersection of Portage Ave. and Vaughan St. Maintain all transit routes and transit stops

FOR INDEX SEE 13362

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES
0 2.5 5 10 15 20 Metres

AECOM REVIEW | DRFT CHK

Saved By:

FILE NAME:

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPR. U/G STRUCTURES COMMITTEE DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

NO.	REVISIONS	YY/MM/DD	BY
0	ISSUED FOR TENDER	23/09/06	ES

AECOM

DESIGNED BY	TB	CHECKED BY	CM
DRAWN BY	ES	APPROVED BY	CM
HOR. SCALE	1:750	RELEASED FOR CONSTRUCTION	
VERT. SCALE	N/A		
DATE		DATE	23-09-14

PLOT DATE:

PROFESSIONAL'S SEAL

PROVINCE OF MANITOBA
T. J. BEAVIS
Member
38263
2023-09-19
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT DRAWING NO.

TENDER No. 599-2023
CONTRACT NUMBER:

FILE PATH:
FILE NAME: 60703129_2023_r0.mxd

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

2023 SEWER RENEWALS BY CIPP LINING
CONTRACT 5
S-MA20016571
PORTAGE AVE
PORTAGE AVE (S.OF CL) TO MH AT VAUGHAN ST TO MH AT TE AT COLONY ST

SHEET 5 OF 15

CITY DRAWING NUMBER
13365 REV 0