

NOTES :

CONSTRUCTION STANDARDS

TO BE CONSTRUCTED IN ACCORDANCE WITH MANITOBA HYDRO DISTRIBUTION AND SUBTRANSMISSION STANDARDS, LATEST REVISION.
NO MAJOR CHANGE SHALL BE MADE WITHOUT APPROVAL OF THE DESIGN ENGINEER OR DELEGATE.

INSTALL NEW STREET LIGHTS AND CABLE ON ALIGNMENT AS SHOWN.

INSTALL NEW GROUND RODS AS PER CD 50-5

ALL STREET LIGHT CABLE TO BE INSTALLED IN 2" CONDUIT

UPON DISCONNECTION BY MB HYDRO THE CONTRACTOR SHALL INSTALL TEMPORARY #6 OVERHEAD FEED IN ORDER TO MAINTAIN LIGHTING DURING CONSTRUCTION. AT THE END OF CONSTRUCTION TEMPORARY OVERHEAD SHALL BE DISCONNECTED BY THE CONTRACTOR.

U/G SL CABLE TO BE MINIMUM 1.0m AWAY FROM ALL OTHER UTILITIES UNLESS OTHERWISE NOTED

MB HYDRO SHALL CUT, CAP AND ABANDON ORIGINAL FEED TO THE STREET LIGHTS PRIOR TO REMOVAL. ALL FINAL CONNECTIONS WILL BE COMPLETED BY MB HYDRO.

INTERSECTION TO BE ADDRESSED ONCE BRUCE CHIN HAS MADE APPROPRIATE CHANGES.

MATCHLINE A

VIEW 1


MATCHLINE A

MATCHLINE B

VIEW 2

PRELIMINARY NOT TO BY USED FOR CONSTRUCTION

CONTACT "CLICK BEFORE YOU DIG MANITOBA" AT ClickBeforeYouDigMB.com
THREE FULL WORKING DAYS PRIOR TO CONSTRUCTION FOR LOCATION OF WATER, WASTEWATER, LAND DRAINAGE UTILITIES AND MANITOBA HYDRO UTILITIES



NO.	DATE	REVISIONS	BY	CHKD.	APP.

AREA 5203, 5201, 5101	MANITOBA HYDRO DISTRIBUTION ENGINEERING
STATION NUMBER N/A	W/O# P:39874 NETWORK # 4308417
FEEDER NUMBER N/A	CSC - CITY CENTRE COW - INKSTER BLVD (EB SINCLAIR TO MAIN) CUSTOMER SERVICE PROJECT
SYSTEM VOLTAGE 120 V	SALVAGE 38-35' 150 W LED STREET LIGHTS AND INSTALL 31-35' 150 W LED STREET LIGHTS
DATE 2024 04 XX	1-04707-DE-50000-0648