

Project Name

Equipment Tag	Description	Training Required	Lamacoid	Shop Drawing Required	Drawing Number
Pumping Station					
SP-M500	Drainage Sump Pump	Yes	Yes	Yes	1-0650Y-M0006-002
CP-M500	Sump pump control panel	Yes	Yes	Yes	1-0650M-E0023-001
DS-AHU-1	AHU-1 Disconnect Switch	No	Yes	Yes	1-0650M-E0003-001
DS-AHU-2	AHU-2 Disconnect Switch	No	Yes	Yes	1-0650M-E0003-001
SW-C700	Chlorine exhaust fan toggle switch (Stairwell)	No	Yes	No	1-0650M-E0023-001
SW-C701	Chlorine exhaust fan toggle switch (Chlorine storage entrance)	No	Yes	No	1-0650M-E0023-001
JB-Y800	Ethernet extender Junction Box	No	Yes	Yes	1-0650M-E0023-001
MS-EEF-1	Chlorine exhaust fan EEF-1 motor starter	No	Yes	Yes	1-0650C-E0004-001
AA-C801	Chlorine detection horn/strobe.	No	Yes	Yes	1-0650M-E0023-001
AA-C802	Chlorine detection horn/strobe.	No	Yes	Yes	1-0650M-E0023-001
CP-C800	Chlorine exhaust fan control panel	Yes	Yes	Yes	1-0650C-E0003-001
DS-EF-M1	Rooftop fan EF-1 disconnect switch	No	Yes	Yes	1-0650M-E0023-001
DS-EF-M2	Rooftop fan EF-2 disconnect switch	No	Yes	Yes	1-0650M-E0023-001
DS-EF-M3	Rooftop fan EF-3 disconnect switch	No	Yes	Yes	1-0650M-E0023-001
DS-CU-1	Rooftop condensing unit disconnect switch	No	Yes	Yes	1-0650M-E0023-001
DS-EEF-1	Chlorine exhaust fan EEF-1 disconnect switch	No	Yes	Yes	1-0650M-E0023-001
DS-FAN-1	Chlorine exhaust fan FAN-1 disconnect switch	No	Yes	Yes	1-0650M-E0023-001
-	Rooftop maintenance receptacles (x4)	No	No	No	1-0650M-E0024-001
-	Chlorine room three way light switch	No	No	No	1-0650M-E0023-001
Lift Station					
P- Y103	Chlorine Sampling Pump	Yes	No	Yes	1-0650Y-M0001-001
HS-Y103	Chlorine sampling pump start/stop pushbutton	No	Yes	Yes	1-0650Y-E0003-001
P-Y101	Chemical Dosing Pump A	Yes	Yes	Yes	1-0650Y-M0001-001
P-Y102	Chemical Dosing Pump B	Yes	Yes	Yes	1-0650Y-M0001-001
SF-Y601	Supply Fan	No	Yes	Yes	1-0650Y-M0002-001
ME-Y601	Dehumidistat	No	Yes	Yes	1-0650Y-E0003-001
MD-Y01	Motorized Damper	No	Yes	Yes	1-0650Y-M0002-001
SPL-Y1	125 A Splitter	No	Yes	Yes	1-0650Y-E0001-001
PNL-Y10	120/240V, 1ph, 3w, 100 A, 18 CCT Panel	No	Yes	Yes	1-0650Y-E0004-001
UH-Y600	Existing 600 V unit heater	No	Yes	No	1-0650Y-E0001-001
JB-Y100	Low level float switch LSL-Y100 junction box	No	Yes	No	1-0650Y-E0003-001
LSL-Y100	Dechlorination chemical batching tank low level float switch	No	Yes	Yes	1-0650Y-E0003-001
LSH-Y802	Wet well high level float switch	No	Yes	Yes	1-0650Y-E0003-001
CP-Y800	Drainage lift station RTU control panel	Yes	Yes	Yes	1-0650Y-E0005-001
-	Automation Junction Box JBA-Y801 auxiliary relays as required	No	No	No	1-0650Y-E0003-001
-	Chemical Dosing Pump P-Y102 simplex receptacle	No	No	No	1-0650Y-E0003-001
-	Drainage lift station 240V, 30 A receptacle	No	No	No	1-0650Y-E0003-001
General Note:					
1. - Not all equipment required for the project is included in the list herein. This is a partial list of main equipment.					
Refer to the drawings and specifications for all equipment requirements.					
2. - Include all costs for the supply and complete installation of all equipment herein, and all equipment shown on the drawings and in the specification.					
3. - Include all costs for new lamacoids, and training.					
4. - In the event of discrepancy between this list and the drawings/specifications, the most onerous and costly option takes precedence prior to clarification from the City.					