



ADDENDUM NO. 2 BID OPPORTUNITY NO. 140-2004

STRATHMILLAN/MOORGATE COMBINED SEWER RELIEF CONTRACT 5

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: May 4, 2004
BY: F. Iwanchuk, UMA Engineering Ltd.
TELEPHONE NO. (204) 284-0580

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: 20040128

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid Submission non-responsive.

PART A – BID SUBMISSION

Replace: Page 7 of Form B: Prices with the attached revised Page 7 of Form B: Prices (R-1).

PART B – BIDDING PROCEDURES

Revise: B2.1 to read:

B2.1 The Submission Deadline is 12:00 noon Winnipeg time, **May 14, 2004**.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D13.3 to read:

D13.3 The Contractor shall commence the Work on Site no later than September 1, 2004.

Revise: D13.3 to read:

D13.4 The City intends to award this Contract by June 2, 2004.

PART E – SPECIFICATIONS

Add E7 as follows:

E7 150 mm TEMPORARY CONCRETE SURFACE RESTORATIONS

E7.1 If the weather will not permit final road pavement restorations to be completed in a timely manner after the underground work, temporary surface restorations for shafts or excavations within the pavement shall be made by installing Temporary Concrete Surface Restorations until such a time as final restorations are complete.

E7.2 Temporary Concrete Surface Restorations shall conform to CW 2130 with the following exception:

- a) No tie bars, dowels or reinforcing steel shall be required.

- E7.3 All shafts and excavations shall be flooded and jetted prior to installing temporary surface restorations.
- E7.4 If the weather will permit, road pavement restorations shall be final restorations and shall commence immediately after underground construction.
- E7.5 Construction of temporary concrete pavement shall be measured on a square metre basis. The amount paid for shall be the total number of square metres of specified thickness acceptably placed. Payment shall be compensation in full for preparation of the base, supplying forms, insulating blankets, as well as supply and placement of Portland cement concrete pavement complete. Payment shall also include removal and disposal of the temporary pavement when permanent restorations commence.