




Rev.	Comments	Jumper or Internal Cable	Conductor #	Cable	Cable Information
0		RIO Repeater			
0		PP1: 03	01-Rx		
0		PP1: 04	01-Tx		
0		PP1: 16	02-Rx		
0		PP1: 15	02-Tx		
0			Coax	01	C-LCP-F01-C01 1-Coaxial RG-6 TO LCP-F01
0		Switch 1			
0			01	RJ-45	C-WTPWSF01 01-C01 4-Pair #24 AWG - Cat 5E TO WTPWSF01 01
0	Spare		02		
0	Spare		03		
0	Spare		04		
0	Spare		05		
0	Spare		06		
0	Plant Monitoring Network Receive	PP1: 05	07-Rx		
0	Plant Monitoring Network Transmit	PP1: 06	07-Tx		
0	Plant Monitoring Network Receive	PP1: 18	08-Rx		
0	Plant Monitoring Network Transmit	PP1: 17	08-Tx		

NOTES:	B.M. ELEV.				 		ENGINEER'S SEAL		THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION	
					DESIGNED BY SWT		CHECKED BY SWT			
					DRAWN BY SWT		APPROVED BY AHL		CITY FILE NUMBER SHEET 32 OF 88	
					SCALE: NTS		RELEASED FOR CONSTRUCTION BY: R. SOROKOWSKI		CITY DRAWING NUMBER 1-0601H-J-A0532-001-01B	
				NO. REVISIONS		DATE BY		CONSULTANT DRAWING NO. WH-A0532		
				1 742-2005 ADDENDUM 6 06/05/25 SWT						
				0 ISSUED FOR TENDER 06/03/29 SWT						



Certificate of Authorization
 Earth Tech Canada Inc.
 No. 730 Expiry: April 30, 2006.