

438-2006 ADDENDUM 1

WINNIPEG TRAFFIC WAYFINDER SIGN SYSTEM – INSTALLATION OF POSTS INCLUDING PILE FOUNDATION

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: July 25, 2006
BY: Coleen Groening
TELEPHONE NO. (204) 986-2491

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20050506

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, July 28, 2006.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D10.1 to read: The Contractor shall achieve Substantial Performance within Forty-Five (45) consecutive Works Days of the commencement of the Work as specified in D9.

Revise: D11.1 to read: The Contractor shall achieve Total Performance within Fifty (50) consecutive Works Days of the commencement of the Work as specified in D9.

PART E – SPECIFICATIONS

Add: E2.2.2(g) All necessary permits and charges required to implement and complete the Work.

Revise: E3.2.11 to read: Nut Covers

The bolts shall be capped with a 1 inch plastic Nut Cover, grey in colour to match Pantone Colour System PMS 429C, as manufactured by Nova Pole International, 203, 26229 Township Road, Spruce Grove, Alberta. Attention: Sandra Atkins, Distributor.

Add to: E3.2.14 The C-5 Coupler is also available for purchase from the City of Winnipeg Stores. Contact Colin Carson, Storekeeper at 986-5372.

Clarification of E3.5.3(c): Delete the last sentence, which reads, "Based on the weather conditions, the Contractor shall temporarily restore the Site to the satisfaction of the Contract Administrator until final restoration."

Add: E4.2.4 The Poles are to be supplied by the City of Winnipeg. The Poles are currently available for pick-up at 1500 Plessis Road, Bridge Maintenance Yard. Contact the Contract Administrator for site access.

Add: E4.2.5 Each pole is identified with a specific engraved Structure Number, (ex. WF001), which corresponds to a specific Site location as specified in E2.3 Location. The poles are stored on pallets in sequential order of installation.