

## 359-2009 ADDENDUM #1

## LANDSCAPING FOR POSITIVE DRAINAGE - VARIOUS INDOOR POOLS

**URGENT** 

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: June 2, 2009 BY: Kathy Roberts TELEPHONE NO. (204) 470-7380

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

## PART D - SUPPLEMENTAL CONDITIONS

Additional scope details for 444 Adsum Drive, Seven Oaks Pool:

Delete: D2.2(f)(ii)

Add: D2.2(f)(iv) Supply and install French drain at mechanical equipment on concrete pad at north side.

Add: D2.2(f)(v) At bay areas on south side of building, supply and install ¾ down crushed rock on

commercial landscape fabric with landscape edging strip. Extend rock 12" past face of

concrete downspout wings.

Additional scope details for 909 Concordia Avenue, Elmwood Kildonan Pool:

Delete: D2.2(g)(iii)

Add: D2.2(g)(iii) Swale around transformer at north side of building.

Add: D2.2(g)(iv) At bay areas on north side of building, supply and install 3/4 down crushed rock on

commercial landscape fabric with landscape edging strip. Extend rock 12" past face of

concrete downspout wings.

Add: D2.2(g)(v) Swale the east side of the building so that water drains to the north or south. Swale

should prevent water run-off into adjacent parking lot.

Additional scope details for 644 Parkdale Street, St. James Centennial Pool:

Revise: D2.2(h)(iv) to read: Replace existing damaged concrete splash pad at east side. Supply and install three (3)

additional splash pads as directed by Contract Administrator.

Clarification of D2.2(h)(v): Concrete pavers at alcoves on east and west sides to be open-cell to match existing.

Add: D2.2(h)(vi) Supply and install approximately forty-five (45) feet of drain tile at southwest wall.

Add: D2.2(i) Removal, storage and re-installation of concrete splash pads at all Work Sites.