



# 983-2012 ADDENDUM 1

## ST VITAL PARK – BOAT LAUNCH REDEVELOPMENT

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY**

ISSUED: January 16, 2013  
BY: Derek Murray  
TELEPHONE NO. (204) 924-3444

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20070419

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

---

### **PART A – BID SUBMISSION**

Replace: 983-2012 Bid Submission with 983-2012 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Item 3 has had the quantities changed and the description changed to better reflect the nature of the Work. Item 9 has had its description changed to better reflect the nature of the Work.

Page numbering on some forms may be changed as a result.

### **DRAWINGS**

Add: 983-2012 \_Drawing\_ Figure1.pdf

### **PART E – SPECIFICATIONS**

- Add: E18.1.3 A sheetpile cofferdam shall be provided for the construction of the pedestal base. The contractor shall provide a drawing for the design of the cofferdam which is signed and sealed by a professional engineer registered in the Province of Manitoba.
- Add: E21. GABION RETAINING WALL
  - E21.1 Materials and Construction Methods
    - E21.1.1 New 1M x1M gabions are to be provided along each side of the new ramp slab as shown in plan on drawings. With reference to Figure 1, the new edge gabions conflict with the existing gabions along the top of the new ramp on the upstream side and the middle of the ramp on the downstream side. The existing gabions on the upstream side are to be removed as required to place the 1M x 1M gabions and rock infill provided to blend with the bank. On the downstream side the existing gabions are to be removed where they conflict with the new 1M x 1M gabions and new gabions shall be provided.
  - E21.2 Materials and Construction Methods
  - E21.3 Method of Measurement and Payment

E21.3.1

Supply and installation of Gabion Retaining walls shall be measured on a per unit basis. The amount to be paid for shall be for completed work, which price shall be for full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and accepted by the Contract Administrator..