

1009-2013 ADDENDUM 1

SUPPLY AND INSTALLATION OF FIBERGLASS SERVICE BODIES

<u>URGENT</u>

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: March 20, 2014 BY: B. Dupuis Smith TELEPHONE NO. 204-986-2492

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A - BID SUBMISSION

Replace: 1009-2013 Bid Submission with 1009-2013 Addendum 1 – Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

FORM N: DETAILED SPECIFICATIONS

| Revise: | 12.5.1 to read: | Body height – nominal 42 in. |
|---------|-----------------|---|
| Revise: | 12.5.3 to read: | Body width – nominal 84 in. |
| Revise: | 12.6.1 to read: | Front vertical compartment – 37"L x 42"H x 15"D approx. c/w three (3) height adjustable shelves. |
| Revise: | 12.6.2 to read: | Horizontal compartment – 40"L x 22"H x 15"D approx., open configuration. |
| Revise: | 12.6.3 to read: | Rear vertical compartment – 31"L x 42"H x 15"D approx., c/w dual swivel material hooks on left, right and rear walls. |
| Revise: | 12.7.1 to read: | Front vertical compartment – 37"L x 42"H x 15"D approx. c/w three (3) height adjustable shelves. |
| Revise: | 12.7.2 to read: | Horizontal compartment – 40"L x 22"H x 15"D approx., with one (1) pullout drawer c/w six (6) dividers. Approx. 5 in. space shall be provided at the bottom for additional tools. |
| Revise: | 12.7.3 to read: | Rear vertical compartment – 31"L x 42"H x 15"D approx., c/w dual swivel material hooks on left, right and rear walls. |
| Revise: | 13.1 to read: | Deck $-\frac{3}{16}$ in. smooth steel. |
| Revise: | 13.3 to read: | Deck sides – 1/8 in. aluminum checkerplate, extended full height up sides of fiberglass side packs. |
| Revise: | 13.5 to read: | Front headboard $-\frac{3}{16}$ in. smooth or checkerplate aluminum construction, full height to top of cab c/w open mesh aluminum for rear window visibility. |