



404-2013 ADDENDUM 1

RE-TILING POOL DECK AND TILING POOL TANK FLOOR AND WALLS FOR MARGARET GRANT POOL – 685 DALHOUSIE

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: September 04, 2013
BY: Anh T. Duong
TELEPHONE NO. 204-986-7588, 204-391-0872

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20130301

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART B – BIDDING PROCEDURE

Revise B2.1 to read: The Submission Deadline is 4:00 p.m. Winnipeg time, September 11, 2013.

PART D – SUPPLEMENTAL CONDITIONS

Revise D17.1 to read: Further to C6.24, the Prime Contractor is PCL.

PART E – SPECIFICATIONS

- | | | |
|-----|----------------------|--|
| Add | E.2.7 | For pool tank |
| | E.2.7.1 | all traces of paint, coatings etc. on walls and floor are to be removed back to a clean concrete surface to all areas within the pool tank area. All paint, coatings are to be removed by sandblasting, shot-blasting or other mechanical means; |
| | E.2.7.2 | apply ¼ inch of flattening coat (kerabond / keralastic) to the pool tank floor to build a flat floor surface for tiling; |
| | E.2.7.3 | remove all existing tiles and thinset on walls (area above water level) and prepare existing concrete once tile is removed; |
| | E.2.7.4 | cover open slots of wall drainage system and all other openings to ensure dust, or any other type of foreign matter does not enter; |
| | E.2.7.5 | all protection of all finishes and areas during the removal is the responsibility of this section; |
| | E.2.7.6
E.2.7.7 | dust and used sand extraction to be the responsibility of this section;
thinset mortar system to be mapei's keralastic / kerabond; grout to be mapei ultracolor; |
| Add | E.3.10 | For pool deck |
| | E.3.10.1 | remove all existing tiles on floor, base, curb and thinset, and prepare of existing concrete once tile is removed; |
| | E.3.10.2 | provide positive slope to the entire pool deck incorporating the existing drains (minimum slope 1/8" per foot); |
| | E.3.10.3 | markings on deck to be 20 cm height; |
| | E.3.10.4
E.3.10.5 | contrasting colour (black) to be installed on top of the curb;
thinset mortar system to be mapei's keralastic / kerabond; grout to be mapei ultracolor |