



## 42-2013 ADDENDUM 1

### SEWPCC VENTILATION AND MISCELLANEOUS UPGRADES

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: April 29, 2013  
BY: Tim Church  
TELEPHONE NO. (204) 786-8080

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20070419

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

---

#### **PART A – BID SUBMISSION**

Replace: 42-2013 Bid Submission with 42-2013\_Addendum\_1\_Bid\_Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): The unit price for Item No. 18, 19 and 20 have been revised to \$32,136, \$8,240, and \$206 respectively.

#### **PART E – SPECIFICATIONS**

Revise: E3.1 In order to expedite Shop Drawings with critical timelines, the Lowest Responsive Bidder, as outlined in B14, **shall**, after receiving written approval from the Contract Administrator, arrange for the preparation of Shop Drawings for the following items with critical timelines:

- (a) Exhaust Fans G686-EF and G687-EF. **Shop drawings to be submitted four weeks after receiving approval from the Contract Administrator.**
- (b) Fire Dampers. **Shop drawings to be submitted four weeks after receiving approval from the Contract Administrator.**

Revise: E3.3 If no contract is awarded, then the City of Winnipeg will pay the requested Bidder up to a maximum of **two thousand dollars (\$2000.00)** for the complete set of requested submissions noted above, for the preparation and delivery of Shop Drawings. Delivery of the Shop Drawings to the City and payment of the above amounts will constitute full and final consideration of each party to the other, and neither party will have any further liability to the other with respect to this Bid Opportunity.

Add: E4.2(b) The total amount of installed insulation used to re-insulate the portions left uncovered from the asbestos abatement Bid Opportunity 40-2013 is estimated to be 979.3 m<sup>2</sup> (10,536 ft<sup>2</sup>). This does not include insulation requirements for new duct work. If the amount of installed insulation actually used is less than 105% of this estimated value, no additional payment will be made. If the amount of installed insulation actually used is more than 105% of the estimated value, then the amount over 105% will be eligible for payment as additional work. The Contractor must submit to the Contract Administrator a detailed account based on measurements of the actual installed insulation used. The Contract Administrator will review the submitted measurements to determine final eligibility for additional payment.

Add: E4.2(c) No additional payment will be made for difficulty of insulation installation.

- Add: E4.8(e) Remove old power and control wiring for G686-EF and G687-EF. Remove old conduit to 300mm outside of hazardous area. Other conduit may remain abandoned in place.
- Revise: E4.8(a)(ii) Motor starters and breakers in existing MCC-1G and MCC-2G for Wet Well Ventilation Upgrades. **Provide a 15 A breaker for spare breakers shown on drawings.**
- Add: E7.8 The use of diesel powered excavation equipment will be permitted in the Boiler Room for the excavation of the new sump pit provided that dust and debris can be contained, exhaust is vented outside, the crane has the capacity to lower the equipment, and noise level issues can be coordinated with operations.
- Add: E13.12 Power for temporary ventilation is the responsibility of the Contractor. The City may provide power from the existing distribution for powering the temporary ventilation subject to connection point availability. Connection points must be approved by the Contract Administrator. Alternatively, a back-up generator may be used for powering of temporary ventilation.

Add 1.2.4 to Section 01 52 00

1.2.4 It is expected that the location of the Contractor's office trailer will be to the south of the SEWPCC facility along the south access road. The exact location will be determined after project award.

Add 1.2.5 to Section 01 52 00

1.2.5 Power will be available from the SEWPCC facility for the Contractor's office trailer. No phone or internet connection will be provided. It is expected that the Contractor will use the cell phone network for both phone and internet connections.

Modify 2.2.1 in Section 23 33 16

2.2.1 Fire dampers: dynamic, "out-of-wall" arrangement, type B style or otherwise with the curtain out of the airstream except where shown on the drawings as "in-the-wall," type A **or multiblade**, listed and bear label of ULC, meet requirements of ANSI/NFPA 90A, and authorities having jurisdiction. Fire damper assemblies fire tested in accordance with CAN4-S112.

## **DRAWINGS**

Replace: 42-2013\_Drawing\_1-0102B-M0001-001-02 with 42-2013\_Addendum\_1\_Drawing\_1-0102B-M0001-001-03

Replace: 42-2013\_Drawing\_1-0102B-M0003-001-01 with 42-2013\_Addendum\_1\_Drawing\_1-0102B-M0003-001-02

Replace: 42-2013\_Drawing\_1-0102G-M0007-001-01 with 42-2013\_Addendum\_1\_Drawing\_1-0102G-M0007-001-02

Replace: 42-2013\_Drawing\_1-0102G-M0011-001-01 with 42-2013\_Addendum\_1\_Drawing\_1-0102G-M0011-001-02

Replace: 42-2013\_Drawing\_1-0102S-M0001-001-01 with 42-2013\_Addendum\_1\_Drawing\_1-0102S-M0001-001-02