



NOTES:

1. DO NOT IMPART EXCESSIVE LOADING ON CLARIFIER WALLS AND UNDERGROUND STRUCTURES. PROVIDE CRANE PAD LOCATIONS AND DESIGN CALCULATIONS TO CONTRACT ADMINISTRATOR FOR REVIEW 2 WEEKS PRIOR TO POSITIONING CRANE.
2. RESTORE SOD, ASPHALT, TREES, SHRUBS, SPRINKLER SYSTEM, ETC. TO EXISTING CONDITION SUBSEQUENT TO THE COMPLETION OF CONSTRUCTION.
3. PROVIDE 100 MM HOUSEKEEPING PADS FOR NEW EXHAUST FANS - REF. MECHANICAL DRAWINGS M0001 AND M0002.
4. REFERENCE MECHANICAL DRAWING M0004 FOR NEW ROOF TOP AIR CONDITIONING UNIT. RESIZE ROOF OPENING TO SUIT.
5. IF ANY CLARIFIER IS EMPTY BETWEEN NOV.1 AND MARCH 30, THE CLARIFIER SHALL BE HOARDED AND HEATED TO MAINTAIN A TEMPERATURE WITHIN THE CLARIFIER OF NOT LESS THAN 10° C.

COWLEGGEND

AS-CONSTRUCTED			
AS-CONSTRUCTED DRAWING REVISIONS ARE BASED SOLELY ON DRAWING MARKUPS OR OTHER FIELD DOCUMENTATION PROVIDED BY THE OWNER. THESE CHANGES HAVE NOT BEEN VERIFIED IN THE FIELD BY KGS GROUP.			

NO.	REVISIONS	DATE	BY
1	ISSUED AS CONSTRUCTED	06/04/10	RJL
0	ISSUED FOR TENDER	13/02/08	RJL

KGS GROUP CONSULTING ENGINEERS & PROJECT MANAGERS	
DESIGNED BY RJL	CHECKED BY
DRAWN BY MB	APPROVED BY
HOR. SCALE: 1:250	RELEASED FOR CONSTRUCTION:
VERTICAL:	DATE: -/12/07

CH2MHILL	
ENGINEER'S SEAL	
THE ORIGINAL ISSUE REV. 0 WAS STAMPED, DATED AND SIGNED R.J. LONG, P.ENG. 13/02/08	
CONSULTANT DRAWING NO. 1-0101P-C0002-001	

THE ORIGINAL ISSUE REV. 0 WAS STAMPED, DATED AND SIGNED R.J. LONG, P.ENG. 13/02/08	
CONSULTANT DRAWING NO. 1-0101P-C0002-001	

THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT	
PROJECT TITLE NORTH END WATER POLLUTION CONTROL CENTRE PRIMARY CLARIFIERS SITE PLAN	
SHEET OF 01 OF 01	KGS JOB NUMBER 06-0107-03
CITY DRAWING NUMBER 1-0101P-C0002-001	