



829-2014 ADDENDUM 1

BROOKSIDE CEMETERY WATER SERVICE RENEWALS

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: September 11, 2014
BY: Bill Nairn, P.Eng.
TELEPHONE NO. (204) 453-2301

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20131129

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 829-2014 Bid Submission with 829-2014 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Add Items A.1 b) i) . **Watermains**, 150 mm (Long Hydrant Lead), Trenchless Installation, Class B Sand Bedding, Class 3 Backfill.

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, September 16, 2014

PART E – SPECIFICATIONS

- Add: E3.4: Items B.1 and B.2 are for the restoration of areas necessary for the completion of the work shown on the plans. Restoration of areas damaged by the Contractor or necessitated by the failure of the Contractor methods or equipment such as the holes to retrieved drilling heads outside of the designated receiving pits will be at the Contractor's expense. No additional compensation will be provided.
- Revise: E5.2: add: If the Contractor is required to shutdown to operations for more than two (2) hours during a given day, that day will not be counted against allowed Working Days provided it is properly logged and verified.
- Revise: E8.2: add: Water Service interior to frost box and buildings to be copper tube, hard drawn, Type L suitable for potable water service.
- Revise: E8.4: add: Because of the proximity to the exterior wall, Contractor to include Frost Box around service to protect from freezing. Frost Box to be 450 mm diameter corrugated galvanized culvert pipe to a minimum depth of 2 m.

Revise: E8.6: to read: Contract Unit Price to be full compensation for all materials and labour necessary to make the connections, install frost box, install meters, restore the floor slab and construction areas and remove or abandon existing service. If there is a charge by the City for the renewing the meter, the Contractor will be reimbursed for the fee charge by the City.

Clarification: Question: Can pipe under Brookside be bell and spigot C900?

Response: The 200 mm watermain is to be fusible PVC in accordance with E9.1. Hydrant leads can be bell and spigot C900 in accordance with The City of Winnipeg Standard Construction Specifications.

Question: Will Dillon Consulting Limited (Dillon) be inspecting connections to the City mains and submitting As-builts to the City in lieu of inspection permits from the City?

Response: Yes, Dillon will be inspecting connections.

Question: Can Contractor install larger diameter sleeve (instead of 25 mm irrigation sleeve) to accommodate multiple different pipe size and material options?

Response: No, irrigation sleeve to be as indicated in plans.

Question: Is the Contractor required to remove the existing tee on the existing 250 mm watermain on Notre Dame Avenue where the existing connection is to be abandoned?

Response: Yes, tee is to be removed in accordance with CW-2110-R11 3.16.3.2.