A1 SIZE – 594mm x 841mm

# ROOM FINISH SCHEDULE

| AREA | SPACE | | FLOOR | | BASE | | | NORTH WALL | | EAST WALL | | SOUTH WALL | | WEST WALL | | CEILING | | | MISCELLANEOUS | | | OTHER REQUIREMENTS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RM NO. | NAME | SUB FLOOR | FIN | HGT | MATL | FIN | MATL | FIN | MATL | FIN | MATL | FIN | MATL | FIN | MATL | FIN | HGT | ITEM | MATL | FIN | |
| HIGH RATE CLARIFICATION BUILDING | K-B02 | GALLERY 5A | CONC | CLR SLR | 100 | | CLR SLR | CONC | CS | CONC | CS | CONC | CS | CONC | CS | CONC | CS | – | – | – | – | SEE NOTE-7 |
| | K-B03 | PUMP ROOM | CONC | CLR SLR | 100 | | CLR SLR | CONC | CS | CONC | SLR | CONC | CS | CONC | CS | CONC | CS | – | – | – | – | SEE NOTE-7 |
| | | | | | | | | | | | | | | | | | | | | | | |
| | K-101 | STAIR | CONC | CLR SLR | 100 | | CLR SLR | CONC | CS | CONC | CS | CONC | CS | CONC | CS | CONC | CS | – | ALUMINUM RAILING AND HANDRAIL | AL | FCTY | SEE NOTE-7 |
| | K-102 | LOADING AREA | CONC | TCTG | 100 | | TCTG | CONC | CS | CONC | CS | CONC | CS | CONC | CS | CONC | CS | – | LOADING DOCK LEVELER | STL | FCTY | SEE NOTE-7 |
| | | | | | | | | | | | | | | | | | | | HORIZONTAL FIRE SHUTTER | STL | PTD | – |
| | K-103 | BALLAST PIT | CONC | TCTG | 100 | | TCTG | CONC | CS | CONC | CS | CONC | CS | CONC | CS | CONC | CS | – | – | – | – | SEE NOTE-7 |
| | K-104 | BALLAST ROOM | CONC | TCTG | 100 | | TCTG | CONC | CS | CONC | CS | CONC | CS | CONC | CS | CONC | CS | – | RAILING | AL | FCTY | FINISH TO LOWERED LEVEL AREA |
| | K-105 | WALKWAY | CONC | TCTG | 100 | | TCTG | CONC | CS | CONC | CS | CONC | CS | CONC | CS | CONC | CS | – | FLOOR ACCESS HATCHES | AL | FCTY | SEE NOTE-7 |
| | K-106 | MECHANICAL ROOM | CONC | CLR SLR | 100 | | CLR SLR | CONC | PTD | CONC | PTD | CONC | PTD | CONC | PTD | CONC | PTD | – | EQUIPMENT PADS | CONC | CLR | SEE NOTE-7 |
| | K-107 | JANITOR'S ROOM | CONC | CLR SLR | – | – | – | CONC | CLR | CONC | CLR | CONC | CLR | CONC | CLR | CONC | CLR | – | FLOOR ACCESS HATCHES | AL | FCTY | – |
| | K-108 | ELECTRICAL ROOM | CONC | CLR SLR | 100 | CONC | CLR SLR | CONC | PTD | CONC | PTD | CONC | PTD | CONC | PTD | CONC | PTD | – | EQUIPMENT PADS | CONC | CLR | SEE NOTE-7 |
| | K-109 | CLARIFIER ROOM | CONC | CONC | 100 | CONC | TCTG | CONC | CS | CONC | CS | CONC | CS | CONC | CS | CONC | CS | – | FLOOR ACCESS HATCHES AND FRP RAILING | AL | FCTY | SEE NOTE-7 |
| | K-110 | SUMP ACCESS ROOM | CONC | CLR SLR | 100 | CONC | CLR SLR | CONC | CS | -- | -- | CMU | CS | CONC | CS | CONC | -- | – | RAILING | AL | FCTY | SEE NOTE-7 |

## ABBREVIATIONS

| | |
|---|---|
| AC | ACOUSTICAL CEILING |
| ACFL | ACCESS FLOORING |
| ACMU | ACOUSTICAL CMU |
| ACT | ACOUSTIC TILE CEILING |
| AFPP | ALUMINUM FACED PLYWOOD PANEL |
| AL | ALUMINUM |
| BRK | BRICK |
| CLR | CLEAR |
| CEMBD | CEMENT BOARD |
| CMU | CONCRETE MASONRY UNITS |
| COL | COLOR |
| CONC | CONCRETE |
| CNTR | COUNTER |
| CPT | CARPET |
| CS | COLORED SEALER |
| CRC | CHEMICAL RESISTANT COATING |
| CT | CERAMIC TILE |
| EIFS | EXTERIOR INSULATION FINIS SYSTEM |
| EXP | EXPOSED STRUCTURE |
| FCTY | FACTORY |
| FRP | FIBERGLASS REINFORCED PLASTIC |
| FWC | FABRIC WALL COVERING |
| FNSH | FINISH |
| GMU | GLASS MASONRY UNITS |
| GCMU | GLAZED CONCRETE MASONRY |
| GWB | GYPSUM BOARD |
| GSB | GYPSUM SOFFIT BOARD |
| GLZ | GLAZING |
| HGT | HEIGHT |
| HDNR | HARDENER |
| MATL | MATERIAL |
| MDO | MEDIUM DENSITY OVERLAY |
| METAL | METAL |
| PLAM | PLASTIC LAMINATE |
| PLAS | PLASTER |
| PAVT | PAVER TILE |
| PLWD | PLYWOOD |
| PNL | PANELING |
| PTD | PAINTED |
| PTN | PARTITION |
| QT | QUARRY TILE |
| RESIL | RESILIENT |
| RRUB | RADIAL RUBBER FLOORING |
| RSF | RUBBER SHEET FLOORING SEALER |
| SF | SPECIAL (SEAMLESS) FLOORING |
| SLR | SEALER |
| SMLS | SEAMLESS EXPOXY |
| SMLQ | SEAMLESS FLOORING (QUARTZ) |
| SOI | SPRAYED – ON INSULATION |
| SVIN | SHEET VINYL |
| TCTG | TRAFFIC COATING |
| TLS | TO LATER SELECTION |
| VCT | VINYL COMPOSITION TILE |
| VT | VINYL TILE |
| VWC | VINYL WALL COVERING |
| X | OPEN |

## GENERAL NOTES

1. PROVIDE ABRASIVE NOSING INSERTS ON ALL STAIRS AND LANDINGS
2. PAINT ALL EXPOSED STEEL STRUCTURE WHICH HAS NOT BEEN GALVANIZED.
3. PAINT U/S OF STAIRS, LANDINGS AND ALL EXPOSED METAL COMPONENTS.
4. EXTENT OF CT ON WALLS MIN. 200mm ABOVE CEILING.
5. COLOUR OF ALL FINISHES: TLS
6. PAINT WALLS BEHIND LOCKERS AND GWB BULKHEAD ABOVE LOCKERS
7. PROVIDE SAWCUT BASE GROOVE ON WALLS AT 100mm ABOVE FLOOR FINISH. SEE DETAIL 2/BDTL-A005.

©CH2M HILL 2017. ALL RIGHTS RESERVED.

APEGM
Certificate of Authorization
CH2M HILL Canada Ltd.
No. 1441

| NO. | REVISIONS | DATE | DESIGN | CHECK |
|---|---|---|---|---|
| 00 | ISSUED FOR CONSTRUCTION – 976-2016 | 2017/04/05 | R.B. | J.C. |

CH2MHILL CANADA Architects Inc.
SNC·LAVALIN
KGS GROUP CONSULTING ENGINEERS

| | |
|---|---|
| DESIGNED BY: R. ZAKKO | CHECKED BY: B. KOLIS-HUPA |
| DRAWN BY: R. BATHAN | APPROVED BY: H.T. FRIEHAMMER |
| SCALE: NTS | ISSUED FOR CONSTRUCTION BY: J. SHUMKA |
| DATE: 2017/04/05 | DATE: 2017/04/05 |
| CONSULTANT NO.: 474248 | |

ENGINEER'S SEAL
PROVINCE OF MANITOBA
REID ZAKKO
04-05-2017
REGISTERED ARCHITECT

Winnipeg
THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

SOUTH END WATER POLLUTION CONTROL CENTRE
SEWPCC UPGRADING/EXPANSION PROJECT
BUILDING
HIGH RATE CLARIFICATION BUILDING
ROOM SCHEDULES

| CITY DRAWING NUMBER | SHEET | REV. | SIZE |
|---|---|---|---|
| 1-0102-BSCH-K001 | 001 | 00 | A1 |

PLOT DATE: 2017\03\30
FILE NAME: 1-0102-BSCH-K001.dgn