A1 SIZE – 594mm x 841mm



BASEMENT FLOOR PLAN

1 : 50





GENERAL NOTES:

1. REFER TO DWG. 1–0102–ELTG–K002–001 FOR LIGHTING GENERAL NOTES.

SPECIFIC NOTES:

1. LUMINAIRE TO BE UN–SWITCHED ON ESSENTIAL LIGHTING CIRCUIT. TYPICAL
2. 3–WAY, MAINTAINED, TOGGLE STYLE LIGHT SWITCH. SEE DWG. 1–0102–ELTG–K004 FOR LIGHTING CONTROL SCHEMATIC.
3. LUMINAIRES TO BE STEM HUNG MOUNTED BELOW THE CABLE TRAY OR PIPE TRAY TO AVOID OBSTRUCTIONS AT AN ELEVATION APPROX. 2500mm ABOVE THE FLOOR.
4. LUMINAIRES TO BE STEM HUNG MOUNTED AT ELEVATION APPROX. 3100mm ABOVE THE FLOOR.
5. LUMINAIRES TO BE PENDANT HUNG MOUNTED AT ELEVATION APPROX. 5100mm ABOVE FLOOR.
6. LUMINAIRES TO BE PENDANT HUNG MOUNTED AT ELEVATION APPROX. 4000mm ABOVE FLOOR.
7. LUMINAIRE TO BE PENDANT HUNG MOUNTED BELOW THE PIPING TO AVOID OBSTRUCTIONS.

REFERENCE DRAWINGS	DESCRIPTION
1–0102–ELTG–K002	LIGHTING PLAN LAYOUT – GROUND FLOOR
1–0102–ELTG–K004	INTERIOR LIGHTING CONTROL SCHEMATIC – CP–K724
1–0102–ESCH–K001	PANEL SCHEDULES & DETAILS
1–0102–ESCH–A002	SCHEDULE – LUMINAIRE AND EXIT SIGNS

1:50 500 0 1000 2000

APEGM Certificate of Authorization
SNC-Lavalin Inc.
No. 4489

NO.	REVISIONS	DATE	DESIGN	CHECK
00	ISSUED FOR CONSTRUCTION – 976–2016	2017/04/05	SLJ	DEB

CH2MHILL. SNC·LAVALIN KGS GROUP

DESIGNED BY: S. JUGANAS	CHECKED BY: E. RYCZKOWSKI
DRAWN BY: MJ. PERSSON	APPROVED BY: D. BECKER
SCALE: 1:50	ISSUED FOR CONSTRUCTION BY: J. SHUMKA
DATE: 2015/02/04	DATE: 2017/04/05
CONSULTANT NO.: 474248	

ENGINEER'S SEAL
PROVINCE OF MANITOBA
D.E. BECKER
Member
23646
REGISTERED PROFESSIONAL ENGINEER
April 5/ 2017

Winnipeg
THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

SOUTH END WATER POLLUTION CONTROL CENTRE
SEWPCC UPGRADING/EXPANSION PROJECT
ELECTRICAL – LIGHTING PLAN LAYOUT
HIGH RATE CLARIFICATION BUILDING
BASEMENT FLOOR PLAN

CITY DRAWING NUMBER	SHEET	REV.	SIZE
1–0102–ELTG–K001	001	00	A1

LAST SAVE: 2017/03/24 – 9:42am
PATH: C:\DWG\1–0102–ELTG–K001.dwg

PLOT DATE: Mar 24, 2017 – 9:42am

FILE NAME: 1–0102–ELTG–K001.dwg