

331-2018 ADDENDUM 3

251 DONALD STREET-ENTRANCE AND EXIT RAMP CONCRETE REPAIRS

<u>URGENT</u>

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY
 ISSUED:
 May 1, 2018

 BY:
 Alan Brenner

 TELEPHONE NO.
 306-343-5500

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

NMS SPECIFICATIONS

Section 07 10 00

Delete: 2.8 Securement Bar

Revise: 3.6.1 to read: Vertical junctures to the deck shall receive a double application of the membrane reinforced with a fully embedded mat of standard reinforcing sheet. The reinforcing sheet shall extend 150mm on the horizontal surface and 150mm up the vertical surface. The second application must overlap the first by 75mm. This work shall be performed prior to application of the membrane layers over full area.

DRAWINGS

Replace: 331-2018_Drawing_M2-R0 with 331-2018_Addendum_3_Drawing_M2-R1