

OFFICE

Enlarged Reflected Ceiling Plan of UTR

A-207 1/4"=1'-0"

GWB 7'-0"

X.Conc. ±11'-5 1/2

GWB 7'-0"

Enlarged Reflected Ceiling Plan of Reception

LIFEGUARD

Contract Administrator. 7. Install all ceiling mounted equipment/ devices on

which cannot be installed as such. 8. Maintain integrity and fire resistance rating of existing beams and columns supporting the main and second floor assembly. Floor assemblies are

established grids of ceiling mounted fixtures or centered within ACT tile. Coordinate on site with

Contract Administrator all equipment/ devices

considered 1 hour rate fire separations. 9. Refer to Room Finish Schedule (A-002) for

finishing requirements in individual spaces. 10. Provide 1/2" Bailey's D-300 reveal trim wherever

GWB abuts adjacent CMU/concrete walls, typical. 11. Coordinate quantity and location of access panels in GWB ceilings with Mechanical and Electrical on

site to meet service access requirements. Not all locations are shown.



The City of Winnipeg 185 King St. Winnipeg, MB R3B 1J1

Rev. No. Date **Revision Notes**

2019.11.06 Issued for Construction

1.) Hoist beam. Refer to Structural. Coordinate

KEY PLAN

exact position and elevation on site to suit material lift.

(2.) Existing roof joist. Typical.

Key Notes

3. GWB clad reccess in bulkhead for track lighting. 4. Pre-finished metal security gate track reccessed into bulkhead. Refer to 2/A-602.

5. Existing concrete beam.

6. Exposed duct. Refer to Mechanical. Refer to 1/A-602 for detail when ducts penetrate GWB.

7. Face of sloped GWB bulkhead up to underside of existing floor slab/roof deck above. Refer to 1 & 2/A-602.

8. Refer to 11/A-601 for rated bulkhead at steel reinforcing of existing beam.

9. Align centre of security grille track to centre of exiting pre-cast rib. 10. Existing column. Provide 1/2" BaileyD-300 GWB reveal trim where GWB abuts column, typical.

1 hour rated GWB bulkhead around mechanical duct within stairwell. Two layers 1/2" type "X" GWB on 2 1/2" metal stud framing to suit.

(12.) 1 hour rated shaftwall ceiling assembly at East Corridor - refer to A-002 for assembly.

(13.) 24" x 24" flush mount fire rated access panels within rated shaftwall ceiling. Coordinate exact location with Electrical on site.

(14.) Flush mount access panel for mechanical equipment service access, typical. Coordinate exact panel size with Mechanical based on equipment size and servicing requirements,

(15.) Existing ACT tile and track to be reinstalled once mechanical and electrical installations are complete. Replace damaged tiles as required.

(16.) Seal top of wall to underside of roof deck and seal new/existing abandoned penetrations to environmentally separate pool spaces from adjacent spaces. Use listed firestop systems at rated walls and smoke separations systems at non-rated walls. Typical.

17.) Provide metal stud framing, bracing and blocking for sliding grille stack space similar to detail 2/A-602 and Structural.

(18.) Patch and make good existing concrete T-slab

preparation for paint finish. (19.) Existing spray applied soundproofing to remain at Auditorium. Carefully remove as required to accommodate mechanical and electrical

(20.) Remove and replace existing GWB ceiling to accommodate sprinkler system installation. No pipes/ heads permitted below 7'-0" above finished floor, typical.

(21.) GWB bulkhead to be finished continuous above

temporary infill wall at future display case. (22.) Mechanical duct to be installed up within T-slab

joist space. (23.) Modify existing rain water leader pipe supports as

required to allow duct to pass above. (24.) Install track light centered on underside of

pre-cast tee. 25. Centre light fixture within ceiling and distribute equally. Typical.

(26.) Centre return grille between light fixture and wall in line with the light fixture in toilet stall. Typical.

(27.) Centre light fixture within ceiling.

(28.) Centre light fixture on sink and mirror below. (29.) Layout ACT in full panels from this corner.



This drawing must not be scaled. The contractors shall verify all dimensions and other data on site prior to commencement of work. Discrepancies, errors, and omissions are to be reported to Public City Architecture Inc. prior to proceeding with the Work.

Drawings and specifications as instruments of service are the property of Public City Architecture Inc.; the copyright in the same being reserved. No reproduction or revision to these drawings may be made without the permission of Public City name. All prints to be returned to Public City Architecture Inc. upon request.

St. James Civic Centre Phase 2 Building Systems Upgrades

MAIN FLOOR REFLECTED CEILING PLAN

Drawn B Reviewed By PS As Noted

Tender No. 1176-2019 Drawing No. 2019.07.01 A-207