

# MONTROSE STREET

100.5 OF 450 CS TO BE LINED  
S-MA60005810



S-MH60004466  
RIM 232.60  
INV N 228.32  
INV S 228.32

CORYDON AVE

S-MH60004458  
RIM 231.78  
INV N 228.90  
INV S 228.90  
**GROUT RISER  
2.2 TO 3.3**

SEWER JUNCTION INFORMATION FROM SEWER VIDEO INSPECTION		
SEWER ID S-MA60005810		
DISTANCE FROM MH ID S-MH60004458		
DISTANCE	DIAMETER	CLOCK
3.6	150	11
5.8	150	11
18.4	150	1
18.6	150	11
33.5	150	11
35.7	150	1
48.2	150	10
49.2	150	1
51.3	250	11
52.2	250	2
64.7	150	10
65.5	150	1
73.4	150	2
79.7	150	11
80.5	150	1
82.4	150	11
93.3	150	11
94.9	150	1

## WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:


- 1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.
- 2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 210/72 FOR DETAILS

FOR INDEX SEE  
12444

## METRIC

WHOLE NUMBERS INDICATE MILLIMETRES  
DECIMALIZED NUMBERS INDICATE METRES



LOCATION APPROVED  
UNDERGROUND STRUCTURES

B.M.  
ELEV.

SUPV. U/G STRUCTURES COMMITTEE DATE

NOTE:

LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

NO.	REVISIONS	DATE	BY

DESIGNED BY	SC	CHECKED BY	SC
DRAWN BY	RS	APPROVED BY	KZ
SCALE:		RELEASED FOR CONSTRUCTION	
HORIZONTAL	1:750		
VERTICAL			
		<b>K. ZUREK</b>	
		DATE	2020-04-22

PLOT DATE: 2020 04 23

ENGINEER'S SEAL

ORIGINAL  
SIGNED BY  
**S.R.J.  
COURNOYER**  
2020/04/17

CONSULTANT DRAWING NUMBER

BID OPPORTUNITY: 197-2020  
CONTRACT NUMBER: 6



## THE CITY OF WINNIPEG

WATER AND WASTE DEPARTMENT  
ENGINEERING DIVISION

2020 SEWER MAIN RENEWALS  
BY CIPP LINING

**MONTROSE STREET**  
2ND MH S PF CROYDON AVENUE TO  
3RD MH S OF CROYDON AVENUE

SHEET 33 OF 60

CITY DRAWING NUMBER

12474