



# 41-2023 ADDENDUM 1

## SNOW CLEARING ON COLLECTOR AND LOCAL STREETS, BACK LANES AND SIDEWALKS WITHIN THE EAST AREA (SOUTH EAST)

### URGENT

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL**

ISSUED: July 12, 2023  
BY: Suzanne Bird  
TELEPHONE NO. 204 986-7507

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

### PART E – SPECIFICATIONS

- Revise: E2.1.9 to read: Snow windrows shall be removed a loader bucket width and a path cleared by back blading to a hard surface from the curb to the sidewalk at a limited number of locations designated as **Accessibility Access to Private Property or Transit Plus Loading Zones**. Location addresses will be supplied to the Contractor after Contract award.
- Revise: E2.3.11 to read: Enhanced Back Lanes identified in Drawing 4 shall be snow cleared full width and hauling away of snow when Priority III streets are cleared as per **D2.4.5**.
- Revise: E2.5.5 to read: Sidewalks shall be cleared to a **full width** and maintained to a compacted snow surface.