



45-2023 ADDENDUM 1

SNOW CLEARING ON REGIONAL AND LOCAL STREETS, BACKLANES AND SIDEWALKS WITHIN THE NORTH AREA (WEST)

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL

ISSUED: July 13, 2023
BY: Ryan Demianiw
TELEPHONE NO. 204 986-7037

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D2.1 to read: The Work to be done under the Contract shall consist of snow clearing supplemental to the City of Winnipeg’s snow clearing operations for the period from **October 15, 2023 until April 15, 2026, with the option of one (1) mutually agreed upon three (3) year extension.**

PART E – SPECIFICATIONS

Revise: E2.1.9 to read: **Snow windrows shall be removed a loader bucket width and a path cleared by back blading to a hard surface from the curb to the sidewalk at a limited number of locations designated as Accessibility Access to Private Property or Transit Plus Loading Zones. Location addresses will be supplied to the Contractor after Contract award.**

Revise: E13.3 to read: Any damage to pavements, boulevards, trees, etc. that in no way present a hazard to either pedestrian or vehicular traffic shall be reported to the Contract Administrator and rectified by the Contractor in accordance with City of Winnipeg specifications prior to June 30th following the snow clearing season. Damages not rectified by June 30th may be rectified by the City or its agents and all costs shall be borne by the Contractor and shall be deducted from monies owing.

Add: E13.3.1: **Damage to tree bark caused by the Contractor while performing Clearing Operations will be assessed an inspection fee of fifty dollars (\$50.00). The fee will be assessed for each instance of bark damage to a given tree. The fee will be adjusted according to E11.**

Add: E13.3.2 **Complete loss of a tree caused by the Contractor while performing Clearing Operations will result in:**

(a) **A fee of seven-hundred-and-fifty dollars (\$750.00) will be assessed. The fee will be adjusted according to E11; or**

(b) **The Contractor will supply and install a replacement tree(s) by October 21st following the date of tree loss with a two (2) year maintenance and warranty, in accordance with the standard requirements for planting trees on City boulevards listed below:**

(i) **Trees are to be planted by a qualified contractor as approved by the Urban Forestry Branch or selected from the list of pre-**

qualified contractors to perform this work on City property. A list of pre-qualified contractors may be viewed at this link:

https://winnipeg.ca/publicworks/parksOpenSpace/UrbanForestry/Homeowner_Tree_Maintenance_Guidelines.stm

- (ii) Trees shall be planted in accordance with the City of Winnipeg Tree Planting Specification and Details:

https://winnipeg.ca/publicworks/parksOpenSpace/UrbanForestry/PDF/Tree_Planting_and_Maintenance_Specification.pdf

Please note the link in Section E13.3.2(b)(ii) (above) is currently broken - all relevant documents are provided below.

https://www.winnipeg.ca/publicworks/parksOpenSpace/UrbanForestry/PDF/SCD-517_Standard_Detail_for_Tree_Planting.pdf

https://www.winnipeg.ca/publicworks/parksOpenSpace/UrbanForestry/PDF/SCD-518_Special_Detail_for_Tree_Planting_with_Tree_Spade_Excavated_Pit.pdf

https://winnipeg.ca/publicworks/parksOpenSpace/UrbanForestry/PDF/SCD-519_Special_Detail_for_Tree_Planting_in_Restricted_Sites.pdf

- (iii) All trees to be planted shall be minimum 50 mm caliper to maximum 70 mm caliper, balled and burlapped nursery-grown stock with associated required root ball diameter, in accordance with the Canadian Nursery Stock Standard issued by the Canadian Nursery Landscape Association.

- (iv) A list of acceptable tree species for planting on City boulevards is located at:

https://winnipeg.ca/publicworks/parksOpenSpace/UrbanForestry/PDF/Acceptable_Tree_Species.pdf

- (v) Specific location and species of tree must be approved by the Urban Forestry Branch prior to planting taking place. The City reserves the right to inspect any trees supplied by the contractor prior to planting and may reject on site if the trees do not meet the standard.

Revise: E14.2 to read:

Where the Contractor does not supply up to the minimum quantity and type of equipment identified in E4 within two hours as outlined in E3.1.6 of the Specifications, the Contractor shall be assessed a penalty of **two thousand dollars (\$2,000.00)** per piece of equipment per call out below the minimum number as specified in E4. The minimum requirement shall apply throughout the duration of the operation from call-out to release of equipment.

APPENDICES

Revise: Appendix E to read:

Appendix E – HISTORICAL WEATHER DATA

<i>YEAR</i>	<i>TOTAL ANNUAL SNOWFALL [CENTIMETER]</i>
1974-1975	125.2
1975-1976	136.2
1976-1977	64.4
1977-1978	73.1
1978-1979	148.6
1979-1980	108
1980-1981	72.5
1981-1982	77.2
1982-1983	77.4
1983-1984	56.3
1984-1985	93.2
1985-1986	124.2
1986-1987	120.2
1987-1988	65.4
1988-1989	153.6
1989-1990	96.4
1990-1991	120.5
1991-1992	133
1992-1993	111.6
1993-1994	82
1994-1995	88.6
1995-1996	202.5
1996-1997	211.4
1997-1998	104.1
1998-1999	144.7
1999-2000	71.4
2000-2001	109.7
2001-2002	105.4
2002-2003	90.9
2003-2004	149.8
2004-2005	136.6
2005-2006	151.2
2006-2007	135.6
2007-2008	111.9
2008-2009	129.2

2009-2010	81.6
2010-2011	149.1
2011-2012	72.6
2012-2013	151
2013-2014	177
2014-2015	82.0
2015-2016	124.0
2016-2017	81.2.
2017-2018	48.8
2018-2019	114.8
2019-2020	150.0
2020-2021	100.8
2021-2022	196.6
