



CONSTRUCTION NOTES:

- 1 REMOVE AND DISPOSE OF EXISTING FENCE (INCIDENTAL),
- 2 EXTEND BARRIER CURB, TIE INTO EXISTING CURB.
- 3 REMOVE EXISTING TREES.
- 4 SAWCUT EXISTING EDGE OF SLAB AS DIRECTED BY CONTRACT ADMINISTRATOR.
- 5 BARRIER CURB TO MODIFIED BARRIER CURB TRANSITION,
- 6 REMOVE EXISTING BERM.
- 7 CONNECT TO EXISTING MANHOLE.
- 8 ALL DIMENSIONS MEASURED TO BACK OF CURB.
- 9 ADJUST ALL MANHOLES AND VALVES.
- 10 ALL CATCHBASINS AS PER SD-024 UNLESS OTHERWISE NOTED.
- 11 PROPOSED CONCRETE SIDEWALK ON 100mm - 19mm DOWN LIMESTONE BASE.
- 12 250mm - DR35 SEWER SERVICE.
- 13 27m - 600mm - 1.6mm GAUGE CORRUGATED STEEL PIPE.
- 14 RAILROAD CROSSING AS PER SD-231A.
- 15 RAILROAD SIDEWALK CROSSING AS PER SD-231B.
- 16 PLACE SUITABLE SITE MATERIAL IN EXISTING DITCH AS PER COW 3170-R4.
- 17 REMOVE EXISTING CULVERT.
- 18 LOWER EXISTING CULVERT TO INVERTS SHOWN AND EXTEND 2m S.

NO.	REVISIONS	DATE
0	ISSUED FOR BIDDING	04.04.16

NO.	REVISIONS	DATE
0	ISSUED FOR BIDDING	04.04.16

WARDROP Engineering Inc.

DESIGNED BY	S.A.M.	CHECKED BY	
DRAWN BY	WRA	APPROVED BY	
HOR. SCALE:	1 : 250	RELEASED FOR CONSTRUCTION	
VERTICAL:	1 : 10		

CONSULTANT DRAWING NO. 031294-01-00

THE CITY OF WINNIPEG
PLANNING, PROPERTY AND DEVELOPMENT

2004 SAINT BONIFACE INDUSTRIAL PARK ROADWORKS
DEBAJETS STREET
STA. 1+20 TO STA. 2+75

APEGIN
Certificate of Authorization
Wardrop Engineering Inc.
No. 195 Expiry: April 30, 2004

CITY DRAWING NUMBER	SHEET 14 OF 16
	C0014