



CONSTRUCTION NOTES:

- ① REMOVE AND DISPOSE OF EXISTING FENCE (INCIDENTAL).
- ② EXTEND BARRIER CURB, TIE INTO EXISTING CURB.
- ③ REMOVE EXISTING TREES.
- ④ SAWCUT EXISTING EDGE OF SLAB AS DIRECTED BY CONTRACT ADMINISTRATOR.
- ⑤ BARRIER CURB TO MODIFIED BARRIER CURB TRANSITION.
- ⑥ REMOVE EXISTING BERM.
- ⑦ CONNECT TO EXISTING MANHOLE.
- ⑧ ALL DIMENSIONS MEASURED TO BACK OF CURB.
- ⑨ ADJUST ALL MANHOLES AND VALVES.
- ⑩ ALL CATCHBASINS AS PER SD-024 UNLESS OTHERWISE NOTED.
- ⑪ PROPOSED CONCRETE SIDEWALK ON 100mm - 19mm DOWN LIMESTONE BASE.
- ⑫ 250mm - DR35 SEWER SERVICE.
- ⑬ 27m - 600mm - 1.6mm GAUGE CORRUGATED STEEL PIPE.
- ⑭ RAILROAD CROSSING AS PER SD-231A.
- ⑮ RAILROAD SIDEWALK CROSSING AS PER SD-231B.
- ⑯ PLACE SUITABLE SITE MATERIAL IN EXISTING DITCH AS PER COW 3170-194.
- ⑰ REMOVE EXISTING CULVERT.
- ⑱ LOWER EXISTING CULVERT TO INVERTS SHOWN AND EXTEND 2m S.

LOCATION APPROVED UNDERGROUND STRUCTURES		DATE
NO.	ISSUED FOR BIDDING	DATE
0	ISSUED FOR BIDDING	04.04.16

NO.	REVISIONS	DATE	BY
0	ISSUED FOR BIDDING	04.04.16	

WARDROP Engineering Inc.

DESIGNED BY: S.A.M.
 DRAWN BY: W.R.A.
 CHECKED BY: [Signature]
 APPROVED BY: [Signature]

SCALE: 1 : 250
 VERTICAL: 1 : 10

CONSULTANT DRAWING NO. 031294-01-00

Winnipeg

THE CITY OF WINNIPEG
 PLANNING, PROPERTY AND DEVELOPMENT

2004 SAINT BONIFACE INDUSTRIAL PARK ROADWORKS
 DEBAETS STREET
 STA. 2+70 TO STA. 3+63.90

CITY DRAWING NUMBER
 SHEET 15 of 16
 C0015

APEGN
 Certificate of Authorization
 Wardrop Engineering Inc.
 No. 195 Expiry: April 30, 2004