

DEMOLITION - KEYNOTES

- 1 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 2 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 3 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 4 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 5 REMOVE EXISTING SIGNAGE PEDESTAL. TURN OVER TO OWNER.
- 6 REMOVE CEILING MOUNTED SIGN.
- 7 REMOVE EXISTING CEILING MOUNTED SECURITY GRILL TRACK AS REQUIRED AND WALL MOUNTED HARDWARE TO SUIT NEW RECONFIGURATION.
- 8 REMOVE EXISTING G.B. CEILING AS REQUIRED TO INSTALL NEW TRACK FOR EXISTING SECURITY GRILL AS PER DETAIL 1/A3.3
- 9 REMOVE EXISTING COAT ROD AND SHELF. REFER TO MILLWORK SCHEDULE THIS PAGE.
- 10 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 11 REMOVE EXISTING BLOCK WALL TO SUIT NEW OPENING REFER TO STRUCTURAL FOR NEW LINTEL.
- 12 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 13 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 14 REMOVE EXISTING COAT ROD AND SHELF.
- 15 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 16 REMOVE EXISTING SHELVING. TURN OVER TO OWNER.
- 17 REMOVE EXISTING SHELVING. TURN OVER TO OWNER.
- 18 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 19 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 20 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 21 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 22 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 23 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 24 REMOVE EXISTING BLOCK WALL TO SUIT NEW OPENING REFER TO STRUCTURAL FOR NEW LINTEL.
- 25 REMOVE EXISTING BLOCK WALL ENCLOSURE.
- 26 REMOVE EXISTING CHAIN LINK ENCLOSURE. TURN OVER TO OWNER.
- 27 REMOVE EXISTING OVERHEAD DOOR, TRACK AND OPERATOR.
- 28 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 29 REFER TO MILLWORK SCHEDULE THIS PAGE.
- 30 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-31.
- 31 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-30.
- 32 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-28.
- 33 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-24.
- 34 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-21.
- 35 REMOVE EXISTING STEEL MESH PARTITION AND DOOR. RECONFIGURE AS REQUIRED FOR REINSTALLATION IN BWPW-03.
- 36 REMOVE EXISTING STEEL MESH PARTITION AND DOOR. RECONFIGURE AS REQUIRED FOR REINSTALLATION IN BWPW-03.
- 37 CUT EXISTING PRECAST PANEL TO SUIT NEW WINDOW.
- 38 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT POPW-38.
- 39 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT BWPW-25.
- 40 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT BWPW-28.
- 41 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-26.
- 42 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-15.
- 43 REMOVE APPROX. 150MM EXISTING MILLWORK TO SUIT RELOCATED DOOR AND EXISTING MILLWORK UNITS.
- 44 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT BWPW-36.
- 45 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-19.
- 46 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT BWPW-03.
- 47 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-03.
- 48 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-16.
- 49 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-03.
- 50 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-33.
- 51 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-05.
- 52 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-05.
- 53 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-23.
- 54 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT TRPW-07.
- 55 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REMOVE GLASS AND MORTAR PATCH AND REPAIR TO MATCH EXISTING. REINSTALL AT TRPW-03.
- 56 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REMOVE GLASS AND MORTAR PATCH AND REPAIR TO MATCH EXISTING. REINSTALL AT TRPW-06.
- 57 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REMOVE GLASS AND MORTAR PATCH AND REPAIR TO MATCH EXISTING. REINSTALL AT TRPW-02.
- 58 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REMOVE GLASS AND MORTAR PATCH AND REPAIR TO MATCH EXISTING. REINSTALL AT TRPW-06.
- 59 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT SAMPW-04.
- 60 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REMOVE GLASS AND MORTAR PATCH AND REPAIR TO MATCH EXISTING. REINSTALL AT SAMPW-09.
- 61 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT SAMPW-09.
- 62 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT SAMPW-02.
- 63 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT POPW-15.
- 64 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT POPW-04.
- 65 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REINSTALL AT POPW-05.
- 66 REMOVE EXISTING DOOR. REINSTALL WITH NEW FRAME AND HARDWARE AT POPW-01.
- 67 REMOVE EXISTING DOOR. REINSTALL WITH NEW FRAME AND HARDWARE. REINSTALL AT POPW-16.
- 68 REMOVE EXISTING DOOR AND HARDWARE. REINSTALL WITH NEW FRAME AT POPW-13.
- 69 REMOVE EXISTING DOOR AND HARDWARE. REINSTALL WITH NEW FRAME AT POPW-11.
- 70 REMOVE EXISTING DOOR, HARDWARE AND FRAME. REMOVE GLASS AND MORTAR PATCH AND REPAIR TO MATCH EXISTING. REINSTALL AT POPW-08.
- 71 REMOVE EXISTING FRENCHISE CABINET. REINSTALL AT NEW LOCATION. REFER TO MCO-3.
- 72 REMOVE EXISTING STEEL GRATE. TURN OVER TO OWNER.
- 73 REFER TO STRUCTURAL FOR DIMENSIONING THE EDGE AND ROUNDOFF OF EXISTING EXTERIOR CONCRETE SLAB FOR BONDED TOPPING AND FLOOR LEVELER APPLICATION.
- 74 NEW DRIVEWAY - REFER TO REFLECTED CEILING PLAN AND STRUCTURAL DRAWINGS FOR EXTENT OF CEILING DISMANTLE/REMOVAL.
- 75 REMOVE EXISTING GATE FRAME.
- 76 REMOVE EXISTING PRE-CAST CONC. PANELS, BASE ANGLE AND METAL PANELS OVER.
- 77 REMOVE EXISTING WINDOWS, PRE-CAST PANEL AND STD WALL ASSEMBLY TO SUIT NEW ADDITION.

| RELOCATED EXISTING MILLWORK SCHEDULE | | |
|--|---------------------------------|--|
| EXISTING LOCATION (LISTED BY DEMO NOTE) | NEW LOCATION (LISTED BY RW NO.) | NOTES |
| 1. Refer to Demo Note 1 (Front Reception) | Lobby TRPW-22 | See plan 72/A3.4 elevations 73 through 76/A3.4 and details 33 through 35/A12.2 for modifications. |
| 2. Refer to Demo Note 2 (Backed Reception) | None | Millwork to be removed and turned over to owner. |
| 3. Refer to Demo Note 3 (Counter) | None | Millwork to be removed and turned over to owner. |
| 4. Refer to Demo Note 4A | None | Millwork to be removed and turned over to owner. |
| 5. Refer to Demo Note 4B | TRPW-12 | Millwork to be removed and relocated. See elevation 80/A3.4 for exact location. |
| 6. Refer to Demo Note 7B | Corridor BWPW-30 | Millwork to be removed and relocated. See Elevation 80/A3.4 for modifications. |
| 7. Refer to Demo Note 7C | Reception BWPW-19 | Millwork to be removed and relocated. No modifications required. |
| 8. Refer to Demo Note 7D | None | Millwork to be removed and turned over to owner. |
| 9. Refer to Demo Note 7E | Meeting Room BWPW-09 | Millwork to be removed and relocated. See Elevation 80/A3.4 for modifications. |
| 10. Refer to Demo Note 7F | None | Millwork to be removed and turned over to owner. |
| 11. Refer to Demo Note 7G | None | Millwork to be removed and turned over to owner. |
| 12. Refer to Demo Note 20 | Meeting Room GENPW-12 | Millwork to be removed and relocated. See Elevation 72/A3.4 for modifications. (One side) |
| 13. Refer to Demo Note 21 | Meeting Room GENPW-12 | Millwork to be removed and relocated. See Elevation 72/A3.4 for modifications. Cap off junction of existing location (see memo). |
| 14. Refer to Demo Note 22 | Reception BWPW-02 | Millwork to be removed and relocated. No modifications required. |
| 15. Refer to Demo Note 23 | Corridor BWPW-12 | Millwork to be removed and relocated. See Elevation 72/A3.4 for modifications. Cap off junction of existing location (see memo). |
| 16. Refer to Demo Note 25 | First Aid Room BWPW-03 | Millwork to be removed and relocated. See Elevation 70/A3.4 for modifications. Cap off junction of existing location (see memo). |
| 17. Refer to Demo Note 26 | None | Millwork to be removed and turned over to owner. |

