

PART E
SPECIFICATIONS

PART E - SPECIFICATIONS

GENERAL

E1. These Specifications shall apply to the Work.

E2. SERVICE

E2.1 Remove the existing flooring from dressing rooms, washrooms, referees room and hallway to a point just south of the dressing room entrance.

E2.2 Dispose of all debris.

E2.3 Prepare floor for new flooring.

E2.4 Install approximately 1363.5 Sq. Ft. of 10mm skate resistant rubber flooring.

E2.5 Seal all edges around walls with suitable caulking.

E2.6 Remove and replace toilets and partitions in washroom.

E2.7 Replace all 4" vinyl baseboard with new baseboard.

E2.8 Colour of flooring shall be marine blue or equivalent.

E3. PRODUCTS

E3.1 Contractors are to supply samples of flooring product with their bid submission.

E4. EMPLOYEE CONDUCT AND SUPERVISION

E4.1 The Contractor shall provide adequate supervision of its employees and shall ensure that all such employees conduct themselves in a manner appropriate to persons in a City facility and shall without limitations ensure that employees:

- (a) Behave in a courteous and polite manner to City staff and other person in the facility;
- (b) Do not smoke within the facility;
- (c) Obey all posted safety rules;
- (d) Leave all furnishings, equipment etc. moved during the inspection and testing, in an "as found" condition at the completion of the work;
- (e) Use their own radio(s) or telephones or cellular telephones necessary for on site communication; and
- (f) When employees are in the facility, that it is kept secure from entry by unauthorized persons.