

PART E
SPECIFICATIONS

PART E - SPECIFICATIONS

GENERAL

E1. APPLICABLE SPECIFICATIONS, STANDARD DETAILS AND DRAWINGS

E1.1 *The City of Winnipeg Works and Operations Division Standard Construction Specifications* in its entirety, whether or not specifically listed on Form B: Prices, shall apply to the Work.

E1.1.1 Division 2 – General Requirements of the City of Winnipeg Works and Operations Division Standard Construction Specifications shall apply to the Work.

E1.1.2 Further to GC:2.4(d), Specifications included in the Tender Package shall govern over the City of Winnipeg Works and Operations Division Standard Construction Specifications.

E1.2 The Appendices in Part F are applicable to the work.

E2. TRUCK WEIGHT LIMITS

E2.1 The City shall not pay for any portion of Material, which results in the vehicle exceeding the maximum gross vehicle weight allowed under *The City of Winnipeg Traffic By-Law*, unless such vehicle is operating under special permit.

E3. JOINT AND CRACK SEALING OF CONCRETE STREETS

E3.1 Further to Division 4 – CW3250-R5, for concrete pavements, place joint sealant 2 millimetres to 4 millimetres above the surface to provide a band-aid seal over the joint or crack. Upon completion, the sealant will overlap either side of the crack by a minimum of 25 millimetres.

E4. CLEAN-UP

E4.1 Further to GC 6.29 Clean-up and Final Cleaning of the Work, the Contractor will be required to carry out power sweeping operations of the Streets once the sealant has cured. In addition, the Contractor will be required to carry out power sweeping operations of the streets where spray type equipment (ie. AMZ machine, Road Patcher machine, etc.) is used in conjunction with emulsified asphalt and aggregates once the repair has cured. Streets to be cleaned will be determined by the Contract Administrator. Street cleaning operations will be considered as incidental to the Works included in this Specification.

E5. TEMPORARY “NO PARKING” SIGNS

E5.1 The contractor shall follow the procedure outlined in Appendix “A” for the placement of temporary “No Parking” signs where required to facilitate the joint and crack sealing operation.

E6. LOCATIONS

E6.1 With respect to locations, the Contractor shall seal the Regional Streets and Local Streets which are identified in Appendix “B”. The Contractor shall also seal the Local Streets identified by the Contract Administrator within the area shown on the maps in Appendix “C”.

The Contractor shall be aware that pending budget funding, locations may be added or deleted.