



# ADDENDUM NO. 1 BID OPPORTUNITY NO. 385-2004

## PROVENCHER PARK ATHLETIC FIELD GRADING

ISSUED: August 16, 2004  
BY: Susan Russell /gfn  
TELEPHONE NO. (204) 956-0396

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: 20040128

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid Submission non-responsive.**

---

### **PART E – SPECIFICATIONS**

Delete: E4.1 (a) The Contractor shall not stockpile materials and soil or park vehicles and equipment within 3 metres of existing trees.

Add: E4.1 (a) The Contractor shall not stockpile materials and soil or park vehicles and equipment within the dripline of existing trees.

Delete: E4.1 (c) Excavation shall be performed in a manner that minimizes damage to the existing root systems. Where possible, excavation shall be carried out such that the edge of the excavation shall be a minimum of 1.5 times the diameter (measured in inches), with the outcome read in feet, from the closest edge of the trunk. Where roots must be cut to facilitate excavation, they shall be pruned neatly at the face of excavation.

Add: E4.1 (c) In areas where significant changes in grade (50mm – 75mm) are proposed within dripline of existing trees, the grade under the dripline shall remain the same and the slope shall be feathered down to the final design grade outside the dripline.

Delete: E4.3 All trees will have a 3m radius protective zone calculated from the circumference at the base of the trunk which will remain free of digging, trenching, grade changes, stock piling of materials and soil compaction throughout the duration of the Contract. Protective fencing around these areas is required

Add: E4.3 All trees will have a protective zone from the base of the trunk to the dripline of the tree, which will remain free of digging, trenching, stockpiling of materials, and soil compaction. Protective snow fencing is required around these areas. In areas where Work need to be done within the dripline, the snow fencing shall be temporarily removed and replaced. This Work shall be done under supervision of the Contract Administrator.