

RUE LANGEVIN

RUE ST. JEAN BAPTISTE

PROVENCHER BOULEVARD

LEGEND

- PROPERTY LINE
- LIMIT OF WORK
- EXISTING SPOT ELEVATION
- PROPOSED SPOT ELEVATION
- PROPOSED CATCH BASIN
- EXISTING CATCH BASIN
- EXISTING CURB INLET
- EXISTING MANHOLE
- EXISTING WATER MAIN
- EXISTING LDS
- APPROX. LIMIT OF GRADING


GENERAL NOTES:

1. CONTRACTOR TO VERIFY ALL DIMENSIONS ON SITE AND REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.
2. CONSTRUCTION ACCESS TO BE LIMITED TO THE ROUTES INDICATED ON THIS PLAN AND AS SPECIFIED ON SITE BY CONTRACT ADMINISTRATOR.
3. CONTRACTOR TO REPAIR ALL SOILED AREAS, CONCRETE, ROAD PAVING, AND CURBS DISTURBED DURING CONSTRUCTION, BOTH ON AND OFF SITE, TO CITY OF WINNIPEG STANDARDS, AT HIS OWN COST
4. REFER ALSO TO WRITTEN SPECIFICATIONS.

GRADING NOTES:

1. CONTRACTOR TO OBTAIN LOCATION OF ALL UTILITIES PRIOR TO ANY CONSTRUCTION.
2. IF POWER EQUIPMENT IS TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST COMPANY OF THE PROPOSED LOCATION OF EXCAVATION. B) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY AND HYDRO COMPANY INSTALLATIONS.
3. CONTRACTOR TO BE ADVISED THAT EXISTING GRADES ARE GIVEN AS INFORMATION ONLY AND SHOULD BE VERIFIED ON SITE. REPORT ANY DISCREPANCIES.
4. ALL GRADING TO BE APPROVED BY CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.
5. ALL ELEVATIONS ARE IN METRIC
6. ALL PROPOSED ELEVATIONS ARE FINISHED ELEVATIONS.
7. EXISTING GRADE TO BE MAINTAINED AT ALL PROPERTY LINES AND CITY SIDEWALK, AND WITHIN 3m OF ALL TREES
8. EXISTING TREES TO BE PROTECTED DURING CONSTRUCTION TO CITY OF WINNIPEG TREE PROTECTION STANDARDS AND GUIDELINES
9. PATHWAY SLOPES: LONGITUDINAL SLOPE - MINIMUM 2% LONGITUDINAL SLOPE - MAXIMUM CROSS SLOPE 2% EXCEPT AS NOTED
10. MAINTAIN EXISTING GRADES AND DRAINAGE PATTERNS. MODIFY CUT AND FILL AS REQUIRED TO ENSURE POSITIVE DRAINAGE OFF OF PATHWAY AND IN ADJACENT SOOLED AREAS.

APREGM
 Certificate of Authorization
 Stantec Consulting Ltd.
 No. 1301 Expiry: April 30, 2005



MCGOWAN RUSSELL
 CLIENT
 BUILDING COMMUNITY
 ST. BONIFACE
 Project Title

ST. BONIFACE
 PARK RENOVATION
 PROJECTS
 SITE WORK

PROVENCHER
 PARK
 SITE SERVICES PLAN

Revision No. _____ Drawing No. **SS1**
 STANTEC DWG. # PP-51-512