



NOTES

1. CONTRACTOR TO CONFIRM LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION.
2. CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.
3. LAYOUT TO BE APPROVED BY CONTRACT ADMINISTRATOR PRIOR TO ANY CONSTRUCTION, OR REMOVALS.
4. ALL DIMENSIONS ARE IN METRIC UNLESS OTHERWISE NOTED. DECIMAL NUMBERS INDICATE METERS.
5. REFER ALSO TO WRITTEN SPECIFICATIONS.
6. REFER TO SITE SERVICES PLAN (SS2) FOR LOCATION OF CATCH BASINS AND MANHOLES.
7. CONTRACTOR TO REPAIR ALL ON AND OFF SITE SODDED AREAS, TREES, CONCRETE, ROAD PAVING AND CURBS ETC., DAMAGED DURING CONSTRUCTION TO CONTRACT ADMINISTRATOR'S SATISFACTION AND TO THE CITY OF WINNIPEG STANDARDS AT HIS OWN COST.
8. CONSTRUCTION ACCESS TO BE LIMITED TO THE ROUTES SPECIFIED ON SITE BY CONTRACT ADMINISTRATOR.
9. REFER TO LAYOUT PLAN FOR LAYOUT OF ALL PATHWAYS, SODDED AREAS AND FENCING.
10. FILL ALL HOLES/DEPRESSIONS LEFT BY EXCAVATION AND REMOVALS OPERATIONS TO DESIGN SUBGRADE ELEVATIONS WITH MATERIAL SUITABLE TO SURFACE FINISH. REFER TO WRITTEN SPECIFICATIONS.

REMOVALS NOTES:

11. IF POWER EQUIPMENT IS TO BE USED FOR EXCAVATION ON THIS PROJECT, THE CONTRACTOR MUST:
 - A) NOTIFY THE GAS COMPANY AND MANITOBA HYDRO OF THE PROPOSED LOCATION OF EXCAVATION.
 - B) TAKE PRECAUTIONS TO AVOID DAMAGE TO GAS AND HYDRO INSTALLATIONS.
12. EXTENT OF CLEARING AND GRUBBING TO BE CONFIRMED ON SITE WITH CONTRACT ADMINISTRATOR.
13. CONTRACTOR TO ESTABLISH GRADE OF EXISTING DRAIN AND SITE FEATURES PRIOR TO EXCAVATION.
14. CONTRACTOR TO ENSURE THAT ALL ITEMS TO BE STOCKPILED DO NOT CAUSE OR SUFFER ANY DAMAGE DURING STORAGE.
15. ALL ITEMS TO BE REMOVED MUST BE DISPOSED OF LEGALLY.
16. CONTRACTOR TO MAINTAIN EXISTING GRADES WITHIN 3m RADIUS OF ALL EXISTING TREES.
17. ALL EXISTING TREES TO REMAIN. CONTRACTOR TO PROTECT TO CITY OF WINNIPEG STANDARDS.
18. SUITABLE GRANULAR BASE COURSE MATERIAL TO BE SALVAGED AND RE-USED AS INSTRUCTED BY CONTRACT ADMINISTRATOR. REFER ALSO TO WRITTEN SPECIFICATIONS.
19. CONTRACTOR TO EXCAVATE FOR ALL NEW WORK SHOWN ON LAYOUT PLAN INCLUDING PATHWAYS, SODDED AREAS, ETC.

LEGEND

- PROPERTY LINE
- - - EXISTING FENCE
- [Hatched Box] AREA OF ROAD AND SIDEWALK REMOVAL
- [Dotted Box] AREA OF BACKLANE REMOVAL
- [Stippled Box] AREA OF REGRADING
- (○) EXISTING TREES TO REMAIN
- (○) EXISTING SHRUBS TO REMAIN
- (○) SHRUBS TO BE REMOVED
- (○) BOLLARD TO BE RELOCATED
- (○) SIGNAGE TO BE REMOVED
- (○) EXISTING SIGNAGE
- (○) STREET LIGHTS TO REMAIN
- (○) EXISTING MANHOLE
- (○) EXISTING CATCH BASIN
- (○) EXISTING WATER VALVE
- (○) EXISTING HYDRANT

2	ISSUED FOR TENDER	12/08/04	SR
1	ISSUED FOR DEVELOPMENT PERMIT	25/05/04	SR
No.	Revisions	Date	By
Date		Scale	
05-21-04		1:500	
Designed By	Drawn By	Checked By	
AH/SR	AH	SR	

Seals

McGOWAN RUSSELL
Client
CITY OF WINNIPEG

BURROWS CENTRAL PARK RENOVATION PROJECT

Sheet Title **SGT. TOMMY PRINCE MM VETERANS PARK REMOVALS PLAN**

Project No. **04-012** Drawing No. **L8**

