



- NOTES :**
1. THESE DRAWINGS SHALL NOT BE SCALED.
 2. THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY HIMSELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.
 3. THE CONTRACTOR IS TO REPORT ANY DISCREPANCIES PRIOR TO COMMENCEMENT OF WORK.
 4. THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.
 5. ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.
 6. ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURERS SPECIFICATIONS & APPLICABLE CODES.
 7. THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.
 8. WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURERS RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.
 9. WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.
 10. ALL NEW LIGHTING FIXTURES & NEW RECEPTACLES TO BE CONNECTED TO APPROPRIATE PANELS, EXCEPT FOR EMERGENCY LIGHT REMOTE HEADS TO BE CONNECTED TO EMERGENCY LIGHT BATTERY PACK(S).
 11. CONTRACTOR MAY REUSE EXISTING BREAKERS & WIRING PROVIDED SAME IS IN GOOD CONDITION & MEETS ALL APPLICABLE CODES.
 12. GENERAL DUTY RECEPTACLES SHALL BE CSA APPROVED BLACK C/W STAINLESS STEEL TRIM PLATES MOUNTED AT 14" FROM FLOOR, EXCEPT FOR GFCI RECEPTACLES.
 13. DIMMERS SHALL BE CSA APPROVED COMMERCIAL SLIDE TYPE TO SUIT CIRCUIT LOAD.
 14. SUPPLY & INSTALL LAMACOID NAME PLATES ON ALL PANEL BOARDS, SWITCHES & RECEPTACLES. PANEL SCHEDULE SHALL BE TYPED & ADHERED TO INSIDE OF ASSOCIATED PANEL DOOR.
 15. ALL ABANDONED ELECTRICAL FIXTURES, COMPONENTS & RECEPTACLE WIRINGS SHALL BE REMOVED BACK TO SOURCE.
- ORIGINAL SEALED BY:**
D.A. Paley P. Eng.
Date: 2004/10/15

ELECTRICAL RENOVATION NOTES:

REFER TO DRAWING E-6 AND NOTES ON DRAWING E-1.

1. SUPPLY & INSTALL DUPLEX RECEPTACLES AS SHOWN IN DARKER LINES. 14" FROM FLOOR OR SAME ELEVATION AS EXISTING. TYPICAL.
2. SUPPLY & INSTALL PHONE WALL OUTLET 14" FROM FLOOR OR SAME ELEVATION AS EXISTING. WHERE PHONE & DATA ARE REQUIRED SIDE-BY-SIDE, USE COMBINATION PHONE & DATA OUTLET- SINGLE GANG BOX. TYPICAL.
3. SUPPLY & INSTALL RANGE RECEPTACLE, 250V/40A.
4. SUPPLY & INSTALL CEILING EXHAUST FAN, NUTONE ULTRA QUIET EXHAUST FAN MODEL LS80. SEE DRAWING M-2 FOR DUCTING.
5. SUPPLY & INSTALL GFCI RECEPTACLE ADJACENT TO NEW VANITY MIRROR.
6. SUPPLY & INSTALL COAXIAL CABLE WALL PLATE AND DUPLEX RECEPTACLE 18" FROM FINISH CEILING. SOURCE OF CABLE TO BE FROM "SHAW" CABLE. EXISTING "SHAW" CABLE BOX IS LOCATED IN TELEPHONE ROOM 223.
7. SUPPLY & INSTALL COAXIAL CABLE WALL PLATE AT SAME ELEVATION AS EXISTING RECEPTACLES ABOVE COUNTER. SOURCE OF CABLE TO BE FROM "SHAW" CABLE. EXISTING "SHAW" CABLE BOX IS LOCATED IN TELEPHONE ROOM 223.
8. SUPPLY & INSTALL JUNCTION BOXES TO UNDERSIDE OF STRUCTURAL CEILING TO ACCOMMODATE SERVICES FOR FUTURE WORKSTATIONS.
9. SUPPLY & INSTALL NEW EXIT LED LIGHTS TO EXISTING EXIT LIGHT WIRING. SEE NEW LIGHT FIXTURE SCHEDULE.
10. SUPPLY & INSTALL NEW CATEGORY 6 DATA CABLES & CONNECTORS TO WALL PLATES & CEILING JUNCTION BOXES AS SHOWN. SEE CATEGORY 6 CABLING SPECIFICATION, DRAWING E-6. ALL CATEGORY 6 CABLING SHALL BE SOURCED FROM THE LAN ROOM 234. THE MAIN SOURCE INTO THE BUILDING IS ON THE MAIN FLOOR COMPUTER ROOM SOUTH OF THE GARAGE AREA. TYPICAL.
11. SUPPLY & INSTALL SMOKE DETECTOR, DIRECT WIRE, EST MODEL EDW1400A IONIZATION DETECTOR

SECOND FLOOR PLAN - ELECTRICAL, DATA & PHONE RENOVATION
SCALE: 1/8" = 1'-0"

NO.	REVISION/DESCRIPTION	BY	DATE

DRAWN BY	DTA	CHECKED BY	APPROVED

CITY OF WINNIPEG
PLANNING, PROPERTY & DEVELOPMENT DEPARTMENT
CIVIC ACCOMMODATIONS DIVISION
300 - 65 GARRY ST. R3C 4K4

PROJECT
Fire Paramedic Services
Executive Office Renovation
185 KING STREET - MANDARIN BLDG.-SECOND FLOOR

ELECTRICAL, DATA & PHONE - RENOVATION

SCALE	PROJECT NO.	SHEET NO.
AS SHOWN	2004-060	E-2