



- NOTES :**
1. THESE DRAWINGS SHALL NOT BE SCALED.
 2. THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY HIMSELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.
 3. THE CONTRACTOR IS TO REPORT ANY DISCREPANCIES PRIOR TO COMMENCEMENT OF WORK.
 4. THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.
 5. ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.
 6. ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURERS SPECIFICATIONS & APPLICABLE CODES.
 7. THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.
 8. WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURERS RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.
 9. WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.
 10. ALL NEW LIGHTING FIXTURES & NEW RECEPTACLES TO BE CONNECTED TO APPROPRIATE PANELS, EXCEPT FOR EMERGENCY LIGHT REMOTE HEADS TO BE CONNECTED TO EMERGENCY LIGHT BATTERY PACK(S).
 11. CONTRACTOR MAY REUSE EXISTING BREAKERS & WIRING PROVIDED SAME IS IN GOOD CONDITION & MEETS ALL APPLICABLE CODES.
 12. GENERAL DUTY RECEPTACLES SHALL BE CSA APPROVED, BLACK C/W STAINLESS STEEL TRIM PLATES MOUNTED AT 14" FROM FLOOR, EXCEPT FOR GFCI RECEPTACLES.
 13. DIMMERS SHALL BE CSA APPROVED COMMERCIAL SLIDE TYPE TO SUIT CIRCUIT LOAD.
 14. SUPPLY & INSTALL LAMACOOD NAME PLATES ON ALL PANEL BOARDS, SWITCHES & RECEPTACLES. PANEL SCHEDULE SHALL BE TYPED & ADHERED TO INSIDE OF ASSOCIATED PANEL DOOR.
 15. ALL ABANDONED ELECTRICAL FIXTURES, COMPONENTS & RECEPTACLE WIRINGS SHALL BE REMOVED BACK TO SOURCE.

ORIGINAL SEALED BY:
 D.A. Paley P. Eng.
 Date: 2004/10/15

NO.	REVISION/DESCRIPTION	BY	DATE

SECOND FLOOR PLAN - ELECTRICAL LIGHTING RENOVATION
 FIRE SPRINKLER HEADS & HVAC GRILLES ARE SHOWN FOR CLARITY.
 SCALE: 1/8" = 1'-0"

ELECTRICAL LIGHTING RENOVATION NOTES:
 REFER TO DRAWING E-6 (ELECTRICAL SPECIFICATION) AND NOTES ON DRAWING E-1.

- 1 RELOCATED FLOURESCENT LIGHTS FROM DEMOLITION. NOTE WIRING. TYPICAL
- 2 NEW LIGHT FIXTURES. WIRE AS SHOWN. TYPICAL
- 3 NEW CEILING EMERGENCY LIGHT. WIRE TO PER EXISTING EMERGENCY LIGHTS.

NEW LIGHT FIXTURE SCHEDULE					
TYPE	QTY.	MANUFACTURER	CATALOGUE No.	LAMP	DESCRIPTION
⊕	6	LIGHTOLIER	1002 1076SBK	75W PAR-30	SHALLOW BLACK BAFFLED DOWNLIGHT, 5 1/4" DIA. CUTOUT
⊕	6	.	.	.	CEILING EMERGENCY LIGHT. MATCH EXISTING TYPE.
EXIT-2	8	LUMACELL	LER450-C860	LED	EXIT SIGN, 120 VOLT INPUT. SINGLE FACE UNIVERSAL MOUNT

DRAWN BY	DATE	CHECKED BY	APPROVED
DTA	2004.10.13	USER APPROVAL	

CITY OF WINNIPEG
 PLANNING, PROPERTY & DEVELOPMENT DEPARTMENT
 CIVIC ACCOMMODATIONS DIVISION
 300 - 65 GARRY ST. R3C 4K4

PROJECT
 Fire Paramedic Services
 Executive Office Renovation
 185 KING STREET - MANDARIN BLDG. - SECOND FLOOR

ELECTRICAL LIGHTING RENOVATION

SCALE	PROJECT NO.	SHEET NO.
AS SHOWN	2004-060	E-4