

## THE CITY OF WINNIPEG

# **BID OPPORTUNITY**

**BID OPPORTUNITY NO. 93 - 2004** 

PROVENCHER BOULEVARD STREETSCAPE DEVELOPMENT

### TABLE OF CONTENTS

#### PART A - BID SUBMISSION

Forn Forn	n A: Bid n B: Prices n G1: Bid Bond and Agreement to Bond n G2: Irrevocable Standby Letter of Credit and Undertaking	1 4 7 9
PART B	- BIDDING PROCEDURES	
B2. B3. B4. B5. B6. B7. B8. B10. B11. B12. B13. B14.	Project Title Submission Deadline Enquiries Addenda Substitutes Bid Submission Bid Prices Qualification Bid Security Opening of Bids and Release of Information Irrevocable Bid Withdrawal of Bids Evaluation of Bids Award of Contract	1 1 1 2 2 3 4 4 5 5 5 6 6 6 7
PART C	- GENERAL CONDITIONS	
C1.	General Conditions	1
	- SUPPLEMENTAL CONDITIONS	
D2. D3. D4. D5.	eral General Conditions Scope of Work Contract Administrator Contractor's Supervisor Notices Furnishing of Documents	1 1 2 2 2 3
<b>Sub</b> D7.	missions Performance Security Insurance	3 3
D9. D10 D11 D12 D13	edule of Work Commencement . Critical Stages . Substantial Performance . Total Performance . Liquidated Damages . Scheduled Maintenance	4 4 4 5 5
D15	<b>trol of Work</b> . Job Meetings . Prime Contractor – The Workplace Safety and Health Act (Manitoba)	5 6
D17	<b>ranty</b> . Warranty n H1: Performance Bond	6 7

Template Version: C120040610

9

Form H2: Irrevocable Standby Letter of Credit

#### **PART E - SPECIFICATIONS**

#### General

E1. Applicable Specifications, Standard Details and Drawings	1
General Requirements	
E2. Traffic Control	2
E3. Pedestrian Safety & Acess To Business	2
E4. Traffic Management	2
E5. Sawcutting Pavement	2
E6. Sign Support Clamps	3 3 3
E7. Winnipeg Transit Bus Stops	3
E8. Construction Facilities and Staging	3
E9. Contractor Employee Parking	3
E10. Work By Others	3
E11. Removals	3
E12. Exposing Existing Underground Services And Utilities	5
E13. Layout of Streetscaping Work	6
E14. Existing Manholes/Curb Stop Boxes/Miscellaneous Adjustments	6
E15. Granular Base Course on Lean Mix Concrete	6
E16. Lean-mix concrete	7
E17. Concrete Formwork	7
E18. Cast In Place Concrete	8
E19. Concrete Collars	11
E20. Unit Pavers	11
E21. Renovated Tree Wells, Tree Trenches, and Planting Bed Preparation	12
E22. Supply And Installation Of Trees, Shrubs And Groundcovers	15
E23. Protection of Existing Trees	20
E24. Landscape Maintenance	21
E25. Dry Laid Limestone Planter	26
E26. Site Furniture	28
E27. Miscellaneous Metal	34