



**CATWALK FRAMING PLAN**  
 SCALE : 1:25  
 GALVANIZED GRATING

STEEL BEAM SCHEDULE			
MARK	SIZE	FINISH	REMARKS
SB-4	MC200x28	PAINTED	CATWALK FRAMING

- NOTES:
- HANGER LOADS FOR JOIST DESIGN:  
 - DEAD LOAD 1.25 kN  
 - LIVE LOAD 8.25 kN
  - LOADS ARE SERVICE LOADS FOR EACH HANGER.

- DRAWING NOTES:
- REFER TO DRAWING S7.01 FOR GRID LINE DIMENSIONS.
  - COORDINATE THE REQUIREMENTS OF CATWALK AND MECHANICAL EQUIPMENT WITH JOIST SUPPLIER.



B.M. ELEV.	NO.	REVISIONS	DATE	BY
	00	ISSUED FOR TENDER	05/12/2	CT



DESIGNED BY	AP/GGP	CHECKED BY	MK
DRAWN BY	CT	APPROVED BY	D. TANIGUCHI
SCALE:	AS NOTED	RELEASED FOR CONSTRUCTION BY:	K. MARTENS
DATE	2005/09/22	DATE	05/12/02

ENGINEER'S SEAL
ORIGINAL SIGNED BY
M. KLASSON
2005/12/02
CONSULTANT DRAWING NO.
CS7.04

**THE CITY OF WINNIPEG**  
 WATER AND WASTE DEPARTMENT  
 ENGINEERING DIVISION

NEWPCC CENTRATE NUTRIENT TREATMENT  
 PHOSPHORUS REMOVAL FACILITY  
 CONTRACT No. 1

STRUCTURAL  
 CHEMICAL STORAGE BUILDING  
 CATWALK FRAMING PLAN & SCHEDULE

CITY FILE NUMBER  
 SHEET OF  
 CITY DRAWING NUMBER  
**1-00F-B-80006-00-00-D**