




Rev.	Comments	Jumper or Internal Cable	Conductor #	Cable	Cable Information	
		PP1				
0	Plant Control Network Receive	Switch 1: 07-Rx	01	C-CP-H11A-C01	12-Strand 62.5/125 um Multi-mode TO LCP-T11A	
0	Plant Control Network Transmit	Switch 1: 07-Tx	02			
0	Spare		03			
0	Spare		04			
0	Plant Monitoring Network Receive	Switch 2: 07-Rx	05			
0	Plant Monitoring Network Transmit	Switch 2: 07-Tx	06			
0	Spare		07			
0	Spare		08			
0	Spare		09			
0	Spare		10			
0	Spare		11			
0	Spare		12			
0	Plant Control Network Transmit	Switch 1: 08-Tx	13	C-CP-D01A-C01	12-Strand 62.5/125 um Multi-mode TO CP-D01A	
0	Plant Control Network Receive	Switch 1: 08-Rx	14			
0	Spare		15			
0	Spare		16			
0	Plant Monitoring Network Transmit	Switch 2: 08-Tx	17			
0	Plant Monitoring Network Receive	Switch 2: 08-Rx	18			
0	Spare		19			
0	Spare		20			
0	Spare		21			
0	Spare		22			
0	Spare		23			
0	Spare		24			

NOTES: 1. Panel and Cabling are not in Contract 742-2005. Drawing Issued for Information Only.	B.M. ELEV.				 		ENGINEER'S SEAL ORIGINAL SIGNED BY S.W. TORMEY 2006/03/29		THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION		
					DESIGNED BY SWT	CHECKED BY SWT	CONSULTANT DRAWING NO. WH-A0506		WATER TREATMENT PLANT PLANT UTILITIES MECHANICAL AND ELECTRICAL		CITY FILE NUMBER
					DRAWN BY SWT	APPROVED BY AHL			AUTOMATION / I AND C PLANT COMMUNICATION CABLE TERMINATION DIAGRAMS		SHEET 6 OF 88
					SCALE: NTS	RELEASED FOR CONSTRUCTION BY: R. SOROKOWSKI			CITY DRAWING NUMBER 1-0601H-J-A0506-001-01B		
				NO. REVISIONS	DATE	BY	DATE 2006/03/29	DATE 2006/03/29			



Certificate of Authorization
Earth Tech Canada Inc.
No. 730 Expiry: April 30, 2006.