CP-P32 DAF Basins 5-8 Control Panel

Rev.	Comments	Jumper or Internal Cable	Switch 1	Conductor #	Cable	Cable Information
0		RJ-45 To PLC	01			
0		RJ-45 To PLC	02			
0			03	RJ-45	C-CP-P32-C01	4-Pair #24 AWG - Cat 5E TO CP-P31A
0			04	RJ-45	C-LCP-P12A-C01	4-Pair #24 AWG - Cat 5E TO LCP-P12A
0			05	RJ-45	C-LCP-P38-C01	4-Pair #24 AWG - Cat 5E TO LCP-P38
0			06	RJ-45	C-LCP-P37-C01	4-Pair #24 AWG - Cat 5E TO LCP-P37
0			07	RJ-45	C-LCP-P36-C01	4-Pair #24 AWG - Cat 5E TO LCP-P36
0			08	RJ-45	C-LCP-P35-C01	4-Pair #24 AWG - Cat 5E TO LCP-P35
0		RJ-45 To Local HMI	09			
0	Spare		10			
0	Spare		11			
0	Spare		12			
0	Spare		13			
0	Spare		14			
0	Spare		15			
0	Spare		16			

NOTES:

1. Panel Supplied by the City.

APEGM
Certificate of Authorization
Earth Tech Canada Inc.
No. 730 Expiry: April 30, 2006.

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
1	742-2005 ADDENDUM 6	06/05/25	SWT
0	ISSUED FOR TENDER	06/03/29	SWT

CH2MHILL
Frederickson Cooper ARCHITECTS
EarthTech A Tyco International Ltd. Company

DESIGNED BY	SWT	CHECKED BY	SWT
DRAWN BY	SWT	APPROVED BY	AHL
SCALE:	NTS	RELEASED FOR CONSTRUCTION BY:	R. SOROKOWSKI
DATE	2006/03/29	DATE	2006/03/29

ENGINEER'S SEAL

ORIGINAL SIGNED BY
S.W. TORMEY
2006/03/29

CONSULTANT DRAWING NO.
WH-A0530

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

WATER TREATMENT PLANT
PLANT UTILITIES
MECHANICAL AND ELECTRICAL

CITY FILE NUMBER

SHEET 30 OF 88

AUTOMATION / I AND C
PLANT COMMUNICATION CABLE
TERMINATION DIAGRAMS

CITY DRAWING NUMBER
1-0601H-J-A0530-001-01B

Thursday, May 25, 2006