



1 Proposed Drainage Works
1:500

1. Layout and Construction Limits to be approved by Contract Administrator prior to construction. Location of drain inlets to be located on-site by Contract Administrator.
2. The Contractor shall locate and mark all underground services prior to construction.
3. All electrical permits and approvals must be in place prior to construction.

LEGEND

- + 231.21 EXISTING SPOT ELEVATION
- + 231.21 PROPOSED SPOT ELEVATION
- - - EXISTING CONTOUR (0.5m INTERVAL)
- - - PROPOSED CONTOUR (0.5m INTERVAL)
- TREE CANOPY
- 62- EXISTING IRRIGATION PIPE - DIA. IN MM.
- EXISTING SPRINKLER, Toro 674-01-72, 634-05-72
- EXISTING SPRINKLER, Toro 634-01-34, 634-06-34
- EXISTING QUICK COUPLING VALVE
- ⊗ EXISTING BUTTERFLY VALVE
- - - EXISTING LIMIT OF FAIRWAY
- - - PROPOSED LIMIT OF FAIRWAY
- - - 100mm DIA. Flexible Drain Pipe
- ADS - 'Nyoplast' Inline Drain (12")
- ↘ 2% PROPOSED DIRECTION OF FLOW (% SLOPE)

THIS DRAWING SHALL NOT BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED ACCORDINGLY
 THE CONTRACTOR SHALL CHECK ALL DIMENSIONS AND OTHER DATA ON SITE AND REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR.
 FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.

DESIGNED BY:	DKM	CHECKED BY:	
DRAWN BY:	DKM	APPROVED BY:	
HOR. SCALE:	As Shown	RELEASED FOR CONSTRUCTION	
VERT. SCALE:			
DATE:	June 22, 2006	CAD FILE:	

SCATLIFF + MILLER + MURRAY
 landscape architecture urban design golf course architecture
 8th floor 44 princess street, winnipeg, mb., r3b 1k2, tel: 204.927.3444 fax: 204.927.3443

DRAWING TITLE	CAD DRAWING NO.
KILDONAN and WINDSOR PARK GOLF COURSE RENOVATIONS - 2006	SHEET 1 OF 1
Kildonan - 4th, 5th and 9th Drainage Works	DRAWING NO.
	K4(G)1