

**SCOPE OF ELECTRICAL WORK**

---

**1. GENERAL**

- .1 Supply and Install all material, equipment, wiring, and labour necessary for the installation of the systems detailed on the Drawings and included in the Specifications in accordance with the latest edition of the Canadian Electrical Code.

**2. WORK INCLUDED**

**2.1 General Requirements**

- .1 General Clean-up.
- .2 All inspection and other permits, licenses required by various Inspection Agencies and local regulations related to Electrical Trade.
- .3 Special testing or inspection, additional to the above as required.
- .4 Scaffolding.
- .5 Shop Drawings.
- .6 Project Record Documents (As-Built Drawings) where specified.
- .7 O&M Data, where specified.

**2.2 Specific Requirements**

- .1 Supply and install roadway lighting as indicated on the Drawings.
- .2 Supply and install parking pedestals and electrical distribution as indicated on the Drawings.
- .3 Supply and install all lighting, lighting controls, and general power as specified herein and indicated on the Drawings.
- .4 Supply and install electrical and communications service at main gate area.
- .5 Supply and install conductor to location of new sign at PR 207.
- .6 Provide all cabling, trenching, and conduit required to make a complete and operational facility.
- .7 Grounding systems, as required by the Manitoba Electrical Code, or as otherwise specified.

**END OF SECTION**