



77-2008 ADDENDUM 3

FORT GARRY TWIN BRIDGES - WESTBOUND STRUCTURE REHABILITATION AND ASSOCIATED ROADWORKS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: March 10, 2008
BY: Rick Haldane-Wilson
TELEPHONE NO. (204) 956-0980

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

Revise: E9.5.5 (d) to read: The deck overhang shall be removed by saw cutting as shown on the Drawings. The concrete surrounding the girder flanges shall be removed by hydrodemolition. The entire vertical concrete surface shall be roughened to a minimum amplitude of 6 mm and a maximum frequency of 15 mm.

DRAWINGS

Replace: 77-2008 _Addendum_2–Drawing_B173-08-025W-R1 with 77-2008 _Addendum_3 –Drawing_B173-08-025W-R2