Perth Ave.

Remove chain from post and chain fence. Replace selected posts

New 1.8m Tache Composite Bench placed in 1.5m x 2.4 m area of crushed limestone paving (50mm cr. fines over 150 mm depth 20 mm down limestone over geotextile

New Jr. Play Structure

New Metal Slat Waste Receptical

Asphalt
Main Area: 69.56 sq m

New Asphalt Paving

New 1.8 m Tache composite bench c.w. armrests

Sod c.w. Topsoil
Main Area: 22.12 sq m

Accessible Entry Point (1.8m width)

1.8 m Tache backless bench c.w. center armrest

New 3.0 m Sandbox

Independent play components (in functional groups) as budget allows.

Two Layer Play Curb (as shown by short dash line -these segments only)

New co-operative Play Component

New Double sided park sign

New 1.8m Tache Composite Bench placed in 1.5m x 2.4 m area of crushed limestone paving (50mm cr. fines over 150 mm depth 20 mm down limestone over geotextile

New Accessible Play Surfacing

New Timber Play curb (single layer with cap except as noted)

Wood Fiber Play Safety Surface
Main Area: 356.66 sq m
Border Area: 11.83 sq m
Perimeter: 79.39 m

New 3 Bay 8' ht. Swing c.w. anti-wrap hangers, 4 belt and 2 infant seats.

Sod c.w. Topsoil
Main Area: 290.88 sq m

3.38

2.16

2.44

2.26

0 5 10 15 m

1
LWC-3

Scale: 1:200
Project Scope Plan

No.	Date	Issue Notes
1	5/28/12	For Bid Opportunity

Drawing No.

LWC-3 of 4

West Kildonan CC Playground

Scope Plan

Dean Spearman
Landscape Architect

11:49:13 AM 5/28/12 West K CC_Working.vwx