North End Water Pollution Control Centre Rehabilitation of Digester No. 11 and Sludge Holding Tank No. 5 and 7 Bid Opportunity No. 573-2012

Part 1 General

1.1 SECTION INCLUDES

.1 Requirements for decommissioning of the existing gas burner and sludge handling equipment. It includes demolition of existing internal structures, salvage of materials and disposal of debris.

1.2 RELATED SECTIONS

- .1 All Sections Division 01
- .2 Division 09 Finishes

1.3 JOB CONDITIONS

- .1 On-site burning will not be permitted.
- .2 Do not use explosives for demolition.

1.4 MEASUREMENT AND PAYMENT

.1 All costs for the work and materials specified in this section shall be included in the lump sum price bid for the Project.

Part 2 Products

Part 3 Execution

3.1 Work

- .1 The work must be coordinated so that the remaining facilities and systems remain operational throughout the project. Any disruptions of service must be agreed to in advance, and notification provided to the Contract Administrator at least two (2) weeks prior to the disruption occurring.
- .2 The existing piping, valves, fittings, supports, concrete, and electrical marked for demolition in the construction drawings shall be decommissioned.
- .3 Those items marked for salvage in the construction drawings shall be turned over to the City of Winnipeg and relocated to an area on site as designated by the City of Winnipeg.
- .4 Any items not marked for salvage on the construction drawings shall be removed from site and disposed of in accordance with all municipal, provincial, and federal codes and regulations.
- .5 All existing piping, valves, fittings, supports, concrete, and electrical not marked for removal on the construction drawings shall be retained.
- .6 Removal of piping, valves, heat trace and electrical equipment may result in the presence of unsealed wall or floor/ceiling openings. Patch all wall and floor/ceiling openings resulting from removal of existing works in accordance with the construction drawings and Division 09 Finishes.

North End Water Pollution Control Centre Rehabilitation of Digester No. 11 and Sludge Holding Tank No. 5 and 7 Bid Opportunity No. 573-2012

3.2 REMOVAL OF DEBRIS

.1 All debris is to be removed from the site and disposed of in accordance with all municipal, provincial, and federal guidelines.

3.3 **PROTECTION**

.1 Use all means necessary to protect existing objects designated to remain and, in the event of damage, make all repairs and replacements necessary, at no change in the Contract Price.

END OF SECTION